

SUMMARY OF QUANTITIES				100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000-2A
CODE NO.	ITEM DESCRIPTION	UNIT			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	310	310	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38	
40600300	AGGREGATE (PRIME COAT)	TON	188	188	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	27	27	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1314	1314	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1277	1277	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7889	7889	
42001300	PROTECTIVE COAT	SQ YD	100	100	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	93917	93917	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	540	540	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	5700	5700	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	500	500	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2800	2800	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1157	1157	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1200	1200	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1240	1240	
55039700	STORM SEWERS TO BE CLEANED	FOOT	1000	1000	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	164	164	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
• 70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
• 70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
• 70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
• 70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
• 70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,271	3,271	
• 70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	932	932	
• 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	58,333	58,333	
• 70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,148	4,148	
• 70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,194	2,194	
• 70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	908	908	

• SPECIALTY ITEM

SUMMARY OF QUANTITIES				100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000
CODE NO.	ITEM DESCRIPTION	UNIT			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,091	1,091	
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	932	932	
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	58,333	58,333	
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,148	4,148	
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,194	2,194	
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	908	908	
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	291	291	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	260	260	
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,462	3,462	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3945	3945	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	75	75	
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5	
55100300	STORM SEWER REMOVAL 8"	FOOT	40	40	
X0517100	STORM SEWERS DUCTILE IRON PIPE 8"	FOOT	40	40	
Z0800150	TRENCH BACKFILL	CU YD	23	23	

• SPECIALTY ITEM

PLOT DATE = 4/16/2009  
 PLOT SCALE = 1:500  
 USER NAME = JFracney  
 MODEL = Default



Excellence through Ownership

200 West Front Street  
 Wheaton, IL 60187

DESIGNED - MAK	REVISED - ---
DRAWN - JMT	REVISED - ---
CHECKED - BLB	REVISED - ---
DATE - 4/16/2009 1:31:20 PM	REVISED - ---

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

LAKE COOK ROAD

SUMMARY OF  
 QUANTITIES

F.A.P. RTE. 1270	SECTION 0506 RS-12	COUNTY LAKE	TOTAL SHEETS 30	SHEET NO. 3
------------------------	-----------------------	----------------	-----------------------	-------------------

CONTRACT NO. 60H02

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

SCALE: SHEET NO. \_\_\_ OF 30 SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

Rev. 5-28-09