

SUMMARY OF QUANTITIES					SUMMARY OF QUANTITIES						
CODE NO.	ITEM	UNIT	URBAN		CONSTRUCTION TYPE CODE	CODE NO.	ITEM	UNIT	URBAN		CONSTRUCTION TYPE CODE
			TOTAL QUANTITIES	1000 100% STATE					TOTAL QUANTITIES	1000 100% STATE	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8108	8108	
40600300	AGGREGATE (PRIME COAT)	TON	50	50		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1788	1788	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	11	11		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	92	92	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	612	612	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2590	2590		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5463	5463	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	470	470		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	550	550	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2030	2030		* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8108	8108	
42001300	PROTECTIVE COAT	SQ YD	367	367		* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1788	1788	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21566	21566		* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	92	92	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2200	2200		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	612	612	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2096	2096		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	100	100	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	416	416		* 78100200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	80	80		* X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	600	600	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1600	1600		* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	800	800	
55039700	STORM SEWERS TO BE CLEANED	FOOT	800	800		* X0322256	TEMPORARY SIGNING INFORMATION	SQ FT	232	232	
60250200	CATCH BASINS TO BE ADJUSTED	EACH	18	18		X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	975	975	
60255500	MANHOLES TO BE ADJUSTED	EACH	18	18		Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	34	34	
60260100	INLETS TO BE ADJUSTED	EACH	18	18		Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	54	54		Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5							
67100100	MOBILIZATION	L SUM	1	1							
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1							
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1							
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	3240	3240							
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	550	550							

* SPECIALTY ITEMS



USER NAME = #USER#	DESIGNED - MJY	REVISED -
PLOT SCALE = #SCALE#	DRAWN - RJG	REVISED -
PLOT DATE = #DATE#	CHECKED - MJY	REVISED -
	DATE - 04/15/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
W 119TH STREET

SCALE: NONE SHEET NO. 3 OF 18 SHEETS STA. 61+00 TO STA. 100+00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1585	2009-048 RS	COOK	18	3
D-91-574-09			CONTRACT NO. 60H18	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		