SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN 100% FED. TOTAL QUANTITY	I000-2A QUANTITY	
20100110	TREE REMOVAL (6 TO 15 UNIT DIAMETER)	UNIT	2,244	2,244	
20100210	TREE REMOVAL (OVER 15 UNIT DIAMETER)	UNIT	5,914	5,914	
20101000	TEMPORARY FENCE	FOOT	2,433	2,433	
20101100	TREE TRUNK PROTECTION	EACH	196	196	
20101200	TREE ROOT PRUNING	EACH	79	79	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	56	56	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	140	140	
20200100	EARTH EXCAVATION	CU YD	34,039	34,039	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	31,512	31,512	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	16	16	
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3,968	3,968	
20800150	TRENCH BACKFILL	CU YD	4,574	4,574	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	68,594	68,594	
21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	30,139	30,139	
25000210	SEEDING,CLASS 2A	ACRE	9.0	9.0	
25000312	SEEDING,CLASS 4A	ACRE	6.3	6.3	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1,697	1,697	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1,697	1,697	
25100630	EROSION CONTROL BLANKET	SQ YD	42,759	42,759	
25200110	SODDING, SALT TOLERANT	SQ YD	25,835	25,835	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	8,160	8,160	
28000300	TEMPORARY DITCH CHECKS	EACH	89	89	
28000400	PERIMETER EROSION BARRIER	FOOT	47,650	47,650	
28000510	INLET FILTERS	EACH	280	280	
28001000	AGGREGATE (EROSION CONTROL)	TON	687	687	
28100105	STONE RIPRAP, CLASS A3	SQ YD	144	144	
28100109	STONE RIPRAP, CLASS A5	SQ YD	27	27	
28100111	STONE RIPRAP, CLASS A6	SQ YD	15	15	
28200200	FILTER FABRIC	SQ YD	1,875	1,875	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	4,972	4,972	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	8,090	8,090	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	200	200	△1
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	60	60	
40600300	AGGREGATE (PRIME COAT)	TON	289	289	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	87	87	

• DENOTES SPECIALTY ITEM

△1 Rev. 5-27-09

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ILLINOIS ROUTE 83
FROM THE WISCONSIN STATE LINE TO
NORTH OF PETITE LAKE ROAD

SUMMARY OF QUANTITIES

SHEET 1 OF 10

DATE: 1/30/09 DRAWN BY: GP CHECKED BY: MW

GRAEF, ANHALT, SCHLOEMER & ASSOCIATES, INC.
CHICAGO, ILLINOIS

G:\20004024_Nvns\planset\sumquan01.dgn
5/4/2009 10:31:26 AM