

ROADWAY\*\*  
 TRAFFIC SIGNALS\*\*  
 RAILROAD BRIDGE\*\*  
 CULVERTS\*\*  
 WEST SIDE BULEYARD  
 MCL ELEM BULWALL  
 SN 045-2038  
 EAST SIDE BULEYARD  
 MCL ELEM BULWALL  
 SN 045-2039\*\*  
 LANDSCAPING\*\*

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODES							
				J00-2A	Y031-1F	X631	Y007	Y007	Y007	Y003	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,080	1,080							
• 44004300	PAVEMENT BREAKING	SQ YD	784	784							
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	213	213							
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	15	15							
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	20	20							
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	82	82							
• 48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1,518	1,518							
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,528	1,528							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1				1				
50104400	CONCRETE HEADWALL REMOVAL	EACH	4					4			
• 50105200	REMOVE EXISTING CULVERTS	EACH	3					3			
50200100	STRUCTURE EXCAVATION	CU. YD.	4,033			1637	740	650	1006		
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2,241				2,241				
50300225	CONCRETE STRUCTURES	CU YD	853	4.5		537		123	188		
• 50300285	FORM LINER TEXTURED SURFACE	SQ FT	7,311					2,958	4353		
• 50300500	DECK DRAINS	FOOT	240			240					
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			1					
50500505	STUD SHEAR CONNECTORS	EACH	1,962			92		750	1120		
• 50700209	UNTREATED TIMBER LAGGING	SQ FT	6,843					2,790	4053		
50800105	REINFORCEMENT BARS	POUND	69,532				69,532				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	115,500	1213		70,670	517	15,380	27720		
△ • 50901105	STEEL RAILING	FOOT	610					207	403		
△ 50901720	BICYCLE RAILING	FOOT	280	280							
△ 50901760	PIPE HANDRAIL	FOOT	284			284					
51202100	FURNISHING STEEL PILES HP12X53	FOOT	1,470			1,470					
• 51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	170					94	76		
• 51202220	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	FOOT	1,834					775	1059		
51202305	DRIVING PILES	FOOT	1,470			1,470					
51203600	TEST PILE STEEL HP12X53	EACH	2			2					
51204650	PILE SHOES	EACH	70			70					
51500100	NAME PLATE	EACH	3			1		1	1		
• 51500110	NAME PLATES (SPECIAL)	EACH	1			1					
54003000	CONCRETE BOX CULVERTS	CU YD	313				313				
54201525	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 60"	FOOT	178	178							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1							
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2							
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1							
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1							
54213915	STEEL END SECTIONS 60"	EACH	8	8							
54244805	INLET BOX, STANDARD 542501	EACH	1	1							
54247130	GRATING FOR CONCRETE FLARED END SECTION 24"	EACH	2	2							
54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	1	1							

• SPECIAL PROVISION     △ SPECIALTY ITEMS  
 •• 80% HPD 20% COUNTY  
 ••• 80% HPP 20% COUNTY

FILE NAME = I:\Dgn\Civil\Sheet\sq002.dgn

USER NAME = tthornton  
 PLOT SCALE = 1:1  
 PLOT DATE = 4/30/2009

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE - 3/27/09

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**KANE COUNTY  
 DIVISION OF TRANSPORTATION**

**NEW STEARNS ROAD - STAGE 2  
 SUMMARY OF QUANTITIES**  
 SCALE: NONE     SHEET NO. 1 OF 7 SHEETS     STA.     TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-10-BR	KANE	219	5
FED. ROAD DIST. NO. 1			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 63073				