150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

720 715 710 705

EX ROW

1:2.5 4% 714.53 4% 1:4

714.19 (EX)
713.93 (PR)

CUT = 11.0 SF
FILL = 0.1 SF
TOPSOIL REMOVAL=6.7 SF

EX ROW

**189 + 50.00**

EX ROW

1:3 4% 714.33 4% 1:4

714.01 (EX)
713.63 (PR)

CUT = 11.1 SF
FILL = 0.1 SF
TOPSOIL REMOVAL=7.3 SF

EX ROW

**189 + 00.00**

EX ROW

1:3 4% 714.10 4% 1:4

713.48 (EX)
713.38 (PR)

CUT = 9.0 SF
FILL = 0.4 SF
TOPSOIL REMOVAL=6.5 SF

EX ROW

**188 + 50.00**

FINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
BY
DATE

ORIGINAL SURVEY
NOTE BOOK
NO.
SURVEYED
PLOTTED
TEMPLATE
AREAS
AREAS CHECKED
BY
DATE

| | | | |
|---|---|---|---|
| FILE NAME = i:\dgn\civil\sheet\xs004.dgn | USER NAME = tthornton | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 1:10 | CHECKED - | REVISED - |
| | PLOT DATE = 3/29/2009 | DATE - 3/27/09 | REVISED - |

**KANE COUNTY**
**DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 31 CROSS SECTIONS**

SCALE: 1"=10'H; 1"=5'V | SHEET NO. 3 OF 6 SHEETS | STA. 188+50.00 TO STA. 189+50.00

| F.A.P RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 361 | 06-00214-10-BR | KANE | 219 | 189 |
| | | CONTRACT NO. 63073 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

XS 31-3