SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	KANE COUNTY QUANTITY	DUPAGE COUNTY QUANTITY	TOTAL QUANTITY	ROADWAY J000-2A IL RTE 25	ROADWAY J000-2A OTHER ROADS	IMPACT ATTENUATORS SFTY-3N	BRIDGE SN 045-2035 X081-2A	BRIDGE SN 045-2032 X081-2A	SFTY-2A	RAIL PROTECTIVE DEVICES SFTY-5A	CMAQ	ITEP
	40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	277		277		277							
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1,734	2,344	4,078	1,180	2,898							
	42000400	PORTLAND CEMENT CONCRETE PAVEMENT 9"	SQ YD	1,152		1,152		1,152							
	42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	36,639		36,639	25,552	11,087							
	42001300	PROTECTIVE COAT	SQ YD	88,046		88,046	29,264	58,782							
	44000100	PAVEMENT REMOVAL	SQ YD	26,872	10,990	37,862	12,335	25,527							
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	7,549		7,549	4,820	2,729							
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4,075	244	4,319	2,942	1,377							
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	514		514	514								
	44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	605		605									605
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	2,531	378	2,909	1,402	1,507							
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,290		1,290	560	730							
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	7,207	2,767	9,974	3,038	6,936							
	48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	287		287	287								
	50100200	REMOVAL OF EXISTING STRUCTURE	L SUM	1		1					1				
	50105220	PIPE CULVERT REMOVAL	FOOT	656	169	825	212	613							
	50200100	STRUCTURE EXCAVATION	CU YD	4,923 △1		4,923 △1					378	2,664 △1			1,881 △1
	50300225	CONCRETE STRUCTURES	CU YD	2,623 △1		2,623 △1				95	489	1,245 △1			814 △1
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,231		1,231				365	866				
	50300260	BRIDGE DECK GROOVING	SQ YD	2,724		2,724				706	2018				
	50300280	CONCRETE ENCASEMENT	CU YD	37		37				9	28				
	50300300	PROTECTIVE COAT	SQ YD	3,151		3,151				846	2305				
	50400905	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 42 IN.	FOOT	1,668		1,668					1,668				
	50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	79		479				479					
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	694,200 △1		694,200 △1				88,670	219,460	237,770 △1			148,300 △1
	50800515	BAR SPLICERS	EACH	1,332		1,332				112	1,029				191
*	50901720	BICYCLE RAILING	FOOT	749		749				130					619
*	50901750	PARAPET RAILING	FOOT	212		212				130					82
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	6,672		6,672				1,584	5,088				
	51202305	DRIVING PILES	FOOT	6,672		6,672				1,584	5,088				
	51203600	TEST PILE STEEL HP12X53	EACH	6		6				2	4				
	51204650	PILE SHOES	EACH	104		104				24	80				
	51500100	NAME PLATES	EACH	4		4				1	1	1			1
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5		5		5							
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	21		21		21							
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	6	2	8	5	3							

△1 Revised 6-8-09

x:\3900s\3944\engineering_documents\General\prpln_ABC-sog_02.dgn

FILE NAME = $FILES$	USER NAME = $USER$	DESIGNED - MAC	REVISED -
		DRAWN - INS	REVISED -
	PLOT SCALE = 1.0000 ' / IN.	CHECKED - JNR	REVISED -
	PLOT DATE = 4/27/2009	DATE - 3/31/09	REVISED -

KANE COUNTY
DIVISION OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-15-BR	KANE/DUPAGE	545	7
		CONTRACT NO. 63074		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		