SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	KANE COUNTY QUANTITY	DUPAGE COUNTY QUANTITY	TOTAL QUANTITY	ROADWAY J000-2A		IMPACT ATTENUATORS SFTY-3N	BRIDGE SN 045-2035 X081-2A	BRIDGE SN 045-2032 X081-2A	SFTY-2A	RAIL PROTECTIVE DEVICES SFTY-5A	CMAQ	ITEP
							IL RTE 25	OTHER ROADS							
	X0301699	STORM SEWER JACKED IN PLACE SPECIAL	FOOT	127		127	127								
	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	74		74	74								
	X0322089	STORM SEWER (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	253		253	253								
	X0322090	STORM SEWER (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	65		65	65								
	X0322125	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	101		101	101								
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	1,610		1,610	644	966							
*	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4,697		4,697								4,697	
	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2		2	2								
*	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	119	9	128	49	79							
*	X0323670	PREFORMED DETECTOR LOOP	FOOT	1,846		1,846	1,846								
*	X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	30,570	6,206	36,776	14,273	22,503							
	X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	148		148					148				
*	X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	5		5	2	3							
*	X0324775	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ.YD.	1,608		1,608	643	965							
*	X0325098	OPTIMIZE TRAFFIC SIGNAL SYSTEM	L SUM	1		1								1	
	X0325598	DRAINAGE SCUPPERS, DS-12M10	EACH	6		6					6				
*	X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	2		2	2								
*	X0325737	TEMPORARY TRAFFIC SIGNAL TIMING △1	EACH	1		1	1								
	X0350810	BOLLARD REMOVAL	EACH	21		21	1	20							
	X0326331	CLEANING AND PAINTING BEARINGS	EACH	13		13									13
	X3120050	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ.YD.	3,841		3,841	1,939	1,902							
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5		5		5							
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE) △1	EACH	12	1	13	12	1							
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	4		4	4								
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	208		208		208							
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	2		2					2				
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	2		2					2				
*	X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	2		2	2								
*	X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1,516		1,516	1,516								
*	XX000366	CLAY LINER	CU FT	315,808	40,440	356,248	57,157	299,091							
	XX000610	RELOCATE EXISTING MAILBOX	EACH	5		5		5							
	XX003988	TEMPORARY CONCRETE BARRIER REMOVAL	FOOT	1,290		1,290		1,290							
	XX004801	BITUMINOUS BIKE PATH REMOVAL	SQ YD	1,270		1,270		1,270							
	XX005277	STORM SEWER, PVC SDR 26, 8"	FOOT	50		50	50								
	XX005449	AGGREGATE SUBGRADE 16"	SQ YD		19,300	19,300		19,300							
*	XX005968	TURBIDITY CURTAIN	SQ YD	100		100		100							
*	XX006257	RECESSED REFLECTIVE PAVEMENT MARKER	EACH		290	290		290							
*	XX006701	SEEDING, CLASS 4 (MODIFIED) MESIC PRAIRIE	ACRE	3	4	7	3	4							
*	XX006702	SEEDING, CLASS 4 (MODIFIED) WET TO MESIC PRAIRIE	ACRE	0.08	0.28	0.36	0.08	0.28							
*	XX006706	SEEDING, CLASS 4 (MODIFIED) DETENTION BASIN	ACRE	4.52	0.27	4.79	0.27	4.52							
*	XX006709	SEEDING, CLASS 5 (MODIFIED) MESIC PRAIRIE	ACRE	2.86	4.00	6.86	0.30	6.56							

△1 Revised 6-8-09

$FILE$

FILE NAME = $FILES$	USER NAME = $USER$	DESIGNED - MAC	REVISED - △1 ADDENDUM 6/5/09	KANE COUNTY DIVISION OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - JNS	REVISED -			361	06-00214-15-BR	KANE/DUPAGE	545	12
	PLOT SCALE = $SCALE$	CHECKED - JNR	REVISED -					CONTRACT NO. 63074		
	PLOT DATE = $DATE$	DATE - 3/31/09	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		