

GUARDRAIL

LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 5	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6B	GUARDRAIL REFLECTORS	BIDIRECTIONAL PRISMATIC BARRIER REFLECTORS	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	CONCRETE BARRIER TRANSITION	BICYCLE RAILING (NOT INCLUDING RAILING ON STRUCTURE)	PAPAPET RAILING (NOT INCLUDING RAILING ON STRUCTURE)	IMPACT ATTENUATORS (NON REDIRECTIVE), TEST LEVEL 3)
	FOOT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	EACH
STA. 489+72.64 (RT) IL-25 / STEARNS RD.					1											
STA. 489+72.64 (RT) IL-25 / STEARNS RD. TO STA. 490+87.94 (RT) IL-25 / STEARNS RD.	112.5									3						
STA. 490+87.94 (RT) IL-25 / STEARNS RD.								1		1						
STA. 490+31.94 (RT) IL-25 / STEARNS RD. TO STA. 491+61.02 (RT) IL-25 / STEARNS RD.											3		30			
STA. 491+21.10 (LT) IL-25 / STEARNS RD.																1
STA. 491+21.10 (LT) IL-25 / STEARNS RD. TO STA. 492+03.05 (LT) IL-25 / STEARNS RD.												82			82	
STA. 492+03.05 (LT) IL-25 / STEARNS RD.											5					1
STA. 505+27.65(RT) IL-25 / STEARNS RD.					1											
STA. 505+27.65 (RT) IL-25 / STEARNS RD. TO STA. 506+27.48 (RT) IL-25 / STEARNS RD.	100									3						
STA. 506+27.48 (RT) IL-25 / STEARNS RD.								1		1						
STA. 506+08.98 (LT) IL-25 / STEARNS RD.					1					2						
STA. 506+66.56 (LT) IL-25 / STEARNS RD.									1							
STA. 506+42.83 (LT) IL-25 / STEARNS RD. TO STA. 506+66.66 (LT) IL-25 / STEARNS RD.														14		
STA. 139+12.70 (LT) IL-25 / STEARNS RD.									1	2						
STA. 139+56.14 (LT) IL-25 / STEARNS RD. TO STA. 140+43.17 (LT) IL-25 / STEARNS RD.	87.5									3						
STA. 140+43.17 (LT) IL-25 / STEARNS RD.				1												
STA. 139+43.28 (LT) IL-25 / STEARNS RD.									1	2						
STA. 139+86.43 (LT) IL-25 / STEARNS RD. TO STA. 143+11.43 (LT) IL-25 / STEARNS RD.	325									9						
STA. 143+11.43 (LT) IL-25 / STEARNS RD.				1												
STA. 139+43.28 (LT) IL-25 / STEARNS RD. TO STA. 140+33.47 (LT) IL-25 / STEARNS RD.														91		
STA. 140+86.10 (RT) IL-25 / STEARNS RD. TO STA. 264+68.16 (LT) DUNHAM RD.		1212.5								31						
STA. 264+25.01 (LT) DUNHAM RD.									1							
STA. 249+17.02 (RT) DUNHAM RD.					1											
STA. 249+17.02 (RT) DUNHAM RD. TO STA. 252+79.52 (RT) DUNHAM RD.	362.5									10						
STA. 252+79.52 (RT) DUNHAM RD.					1					2						
STA. 251+01.24(RT) DUNHAM RD. TO STA. 253+09.81 (RT) DUNHAM RD.														209		
STA. 253+91.17 (LT) DUNHAM RD.				1												
STA. 253+91.17 (LT) DUNHAM RD. TO STA. 262+03.67 (LT) DUNHAM RD.		812.5								0						
STA. 262+18.34 (LT) DUNHAM RD.								1		1						
STA. 259+86.65 (RT) DUNHAM RD.				1												
STA. 259+86.65 (RT) DUNHAM RD. TO STA. 261+24.08 (RT) DUNHAM RD.	137.5									4						
STA. 261+67.23 (RT) DUNHAM RD.								1		2						
STA. 260+76.01 (RT) DUNHAM RD.				1												
STA. 260+76.01 (RT) DUNHAM RD. TO STA. 261+13.51 (RT) DUNHAM RD.	37.5									2						
STA. 261+56.73 (RT) DUNHAM RD.								1		1						
STA. 261+92.86 (LT) DUNHAM RD.						1										
STA. 262+07.53 (LT) DUNHAM RD.									1							
STA. 263+63.47 (RT) DUNHAM RD.										1						
STA. 263+78.14 (RT) DUNHAM RD.									1							
STA. 263+74.22 (RT) DUNHAM RD.										1						
STA. 263+88.89 (RT) DUNHAM RD.									1							
STA. 264+14.52 (LT) DUNHAM RD.									1	2						
STA. 264+57.66 (LT) DUNHAM RD. TO STA. 265+95.17 (LT) DUNHAM RD.	137.5									4						
STA. 265+95.17(LT) DUNHAM RD.				1												

x:\9900a\9944\enq\enr\inc_documents\genera\ypr\pin_ABC_schog_05.dgn