

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	KANE COUNTY QUANTITY	DUPAGE COUNTY QUANTITY	TOTAL QUANTITY	ROADWAY J000-2A		IMPACT ATTENUATORS SFTY-3N	BRIDGE SN 045-2035 X081-2A	BRIDGE SN 045-2032 X081-2A	SFTY-2A	RAIL PROTECTIVE DEVICES SFTY-5A	CMAQ	ITEP
							IL RTE 25	OTHER ROADS							
*	85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	2		2	2								
*	86000105	MASTER CONTROLLER (SPECIAL)	EACH	1		1									1
*	86400100	TRANSCEIVER - FIBER OPTIC	EACH	2		2									2
*	87100160	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 24F	FOOT	4,697		4,697									4,697
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	409		409	409								
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	409		409	409								
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	7,795		7,795	7,795								
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3,244		3,244	3,244								
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	7,743		7,743	7,743								
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	220		220	220								
*	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1		1	1								
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	4		4	4								
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	6		6	6								
*	87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1	1								
*	87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1		1	1								
*	87700414	STEEL MAST ARM ASSEMBLY AND POLE, 66 FT.	EACH	3		3	3								
*	87700430	STEEL MAST ARM ASSEMBLY AND POLE, 75 FT.	EACH	1		1	1								
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	44		44	44								
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8		8	8								
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15		15	15								
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	15		15	15								
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	18		18	18								
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10		10	10								
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	9		9	9								
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4		4	4								
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2	2								
*	88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	22		22	22								
*	88500100	INDUCTIVE LOOP DETECTOR	EACH	21		21	21								
*	88600100	DETECTOR LOOP, TYPE I	FOOT	354		354	354								
*	88800100	PEDESTRIAN PUSH-BUTTON	EACH	2		2	2								
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1	1								
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2	2								
*	89502380	REMOVE EXISTING HANDHOLE	EACH	3		3	3								
*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	6		6	6								
*	K0038000	PERENNIAL PLANTS, WETLAND EMERGENT TYPE	UNIT	257	16	273	14	259							
*	K1004485	PERENNIAL PLANTS, WETLAND TYPE	UNIT	259	16	276	14	262							

x:\39003\3644\enr\enr\eng\documents\general\p\p\in\ABC_soa_05.dgn

FILE NAME =	USER NAME = #USER#	DESIGNED - MAC	REVISED -	KANE COUNTY DIVISION OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILES#		DRAWN - INS	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	KANE/DUPAGE	545	11
	PLOT SCALE = 1:8000' / IN.	CHECKED - JNR	REVISED -						FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	CONTRACT NO. 63074	
	PLOT DATE = 4/27/2009	DATE - 3/31/09	REVISED -										