M.O.T. TEMPORARY PAVEMENT

STAGE AND LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE B (12")	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (10")	AGGREGATE SHOULDERS, TYPE B 8"
	CU YD	TON	SQ YD
STAGE 1A			
STEARNS RD.			
170+50 TO 179+00	462	777	378
STAGE 2A			
IL 25/STEARNS RD.			
502+00 TO 505+00	229	385	133
IL 25			
280+00 TO 281+00	64	107	44
282+00 TO 289+00	360	605	311
STEARNS RD.			
168+50 TO 171+00	128	216	0
EX. DUNHAM RD.			
410+00 TO 416+00	270	453	267
416+00 TO 417+50	55	92	0
TOTAL	**1,568**	**2,634**	**1,133**

M.O.T. TEMPORARY IMPACT ATTENUATORS

STAGE AND LOCATION	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2
	EACH	EACH
STAGE 1A		
DUNHAM RD.		
428+00	4	
FROM 415+00 TO 420+25		1
FROM 434+20 TO 425+00		1
STEARNS RD.		
185+68	1	
186+72	1	
194+76	1	
STAGE 2A		
STEARNS RD.		
1223+00		1
STAGE 2B		
DUNHAM RD.		
274+00		1
279+00		1
STEARNS RD.		
501+50		1
TOTAL	**7**	**6**

M.O.T. TEMPORARY CONCRETE BARRIER

STAGE AND LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
	FOOT	FOOT
STAGE 1A		
DUNHAM RD.		
415+80 TO 420+25	545	
425+00 TO 427+65	265	
427+89 TO 432+80	493	
434+20 TO 436+00	180	
STEARNS RD.		
168+00 TO 185+63	1,763	
186+72 TO 194+76	804	
STAGE 2A		
STEARNS RD.		
1223+00 TO 1229+00		600
STAGE 2B		
DUNHAM RD.		
274+40 TO 279+00		460
STEARNS RD.		
501+00 TO 139+41		752
TOTAL	**4,050**	**1,812**

x:\3900s\3944\engineering documents\general\prpln_ABC_sched08.dgn

FILE NAME = $FILES$	USER NAME = $USER$	DESIGNED - MAC	REVISED -	**KANE COUNTY DIVISION OF TRANSPORTATION**	**SCHEDULE OF QUANTITIES**
		DRAWN - VLM	REVISED -		
	PLOT SCALE = 1.0000 ' / IN.	CHECKED - JNR	REVISED -		
	PLOT DATE = 3/30/2009	DATE - 3/31/09	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
361	06-00214-15-BR	KANE/DUPAGE	545	43
		CONTRACT NO. 63074		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		