

EARTH EXCAVATION ---- STEARNS ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
485+09.91	49.73	596.43					
485+50.00	48.10	583.42	48.92	589.93	40.09	72.63	875.93
486+00.00	41.29	347.74	44.70	465.58	50.00	82.77	862.19
486+50.00	52.31	173.27	46.80	260.51	50.00	86.67	482.42
487+00.00	40.16	541.81	46.24	357.54	50.00	85.62	662.11
487+50.00	35.77	463.15	37.97	502.48	50.00	70.31	930.52
488+00.00	36.89	288.34	36.33	375.75	50.00	67.28	695.82
488+50.00	36.96	311.01	36.93	299.68	50.00	68.38	554.95
489+00.00	40.56	336.89	38.76	323.95	50.00	71.78	599.91
489+50.00	35.60	245.86	38.08	291.38	50.00	70.52	539.58
490+00.00	114.54	151.97	75.07	198.92	50.00	139.02	368.36
490+50.00	148.52	50.74	131.53	101.36	50.00	243.57	187.69
491+00.00	39.09	23.36	93.81	37.05	50.00	173.71	68.61
491+50.00	26.69	0.65	32.89	12.01	50.00	60.91	22.23
492+00.00	88.34	25.52	57.52	13.09	50.00	106.51	24.23
492+50.00	73.86	108.17	81.10	66.85	50.00	150.19	123.79
493+00.00	82.50	11.02	78.18	59.60	50.00	144.78	110.36
493+50.00	76.32	30.06	79.41	20.54	50.00	147.06	38.04
494+00.00	98.15	38.27	87.24	34.17	50.00	161.55	63.27
494+50.00	129.90	27.22	114.03	32.75	50.00	211.16	60.64
495+00.00	150.92	19.64	140.41	23.43	50.00	260.02	43.39
495+50.00	281.54	10.41	216.23	15.03	50.00	400.43	27.82
496+00.00	445.81	18.48	363.68	14.45	50.00	673.47	26.75
496+50.00	508.77	1.12	477.29	9.80	50.00	883.87	18.15
497+00.00	496.15	4.03	502.46	2.58	50.00	930.48	4.77
497+50.00	416.84	4.15	456.50	4.09	50.00	845.36	7.57
498+00.00	322.13	16.66	369.49	10.41	50.00	684.23	19.27
498+50.00	235.87	31.39	279.00	24.03	50.00	516.67	44.49
499+00.00	138.14	58.85	187.01	45.12	50.00	346.31	83.56
499+50.00	13.61	62.59	75.88	60.72	50.00	140.51	112.44
500+00.00	36.14	20.84	24.88	41.72	50.00	46.06	77.25
500+50.00	31.09	80.58	33.62	50.71	50.00	62.25	93.91
501+00.00	50.60	146.67	40.85	113.63	50.00	75.64	210.42
501+50.00	64.03	247.94	57.32	197.31	50.00	106.14	365.38
502+00.00	96.99	314.90	80.51	281.42	50.00	149.09	521.15
502+50.00	136.00	380.54	116.50	347.72	50.00	215.73	643.93
503+00.00	148.67	490.78	142.34	435.66	50.00	263.58	806.78
503+50.00	177.42	588.94	163.05	539.86	50.00	301.94	999.74
504+00.00	322.90	731.25	250.16	660.10	50.00	463.26	1222.40
504+50.00	229.44	949.16	276.17	840.21	50.00	511.43	1555.94
505+00.00	140.68	1192.89	185.06	1071.03	50.00	342.70	1983.38
505+50.00	52.52	1363.93	96.60	1278.41	50.00	178.89	2367.43
506+00.00	106.39	1334.59	79.46	1349.26	50.00	147.14	2498.63
506+50.00	6.54	1222.88	56.47	1278.74	50.00	104.56	2368.03

EARTH EXCAVATION ---- STEARNS ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
139+50.00	4.51	1563.16					
140+00.00	8.89	1275.95	6.70	1419.56	50.00	12.41	2628.81
140+50.00	3.37	1343.57	6.13	1309.76	50.00	11.35	2425.48
141+00.00	54.51	1318.92	28.94	1331.25	50.00	53.59	2465.27
141+50.00	654.56	997.86	354.54	1158.39	50.00	656.55	2145.17
142+00.00	500.34	758.63	577.45	878.25	50.00	1069.35	1626.38
142+50.00	454.32	347.34	477.33	552.99	50.00	883.94	1024.05
143+00.00	277.80	79.25	366.06	213.30	50.00	677.89	394.99
143+50.00	367.38	482.03	322.59	280.64	50.00	597.39	519.70
144+00.00	277.26	1038.94	322.32	760.49	50.00	596.89	1408.31
144+50.00	41.04	1345.68	159.15	1192.31	50.00	294.72	2207.98
145+00.00	212.97	1784.02	127.01	1564.85	50.00	235.19	2897.87
145+50.00	169.81	2268.19	191.39	2026.11	50.00	354.43	3752.05
146+00.00	21.27	2600.02	95.54	2434.11	50.00	176.93	4507.60
146+50.00	28.33	3034.56	24.80	2817.29	50.00	45.93	5217.20
147+00.00	44.67	3519.96	36.50	3277.26	50.00	67.59	6069.00
147+50.00	0.00	4162.39	22.34	3841.18	50.00	41.36	7113.29
148+00.00	533.72	3145.89	266.86	3654.14	50.00	494.19	6766.93
148+50.00	361.55	2500.30	447.64	2823.10	50.00	828.95	5227.95
149+00.00	362.96	1718.34	362.26	2109.32	50.00	670.84	3906.15
149+50.00	1222.84	0.04	792.90	859.19	50.00	1463.33	1591.09
150+00.00	270.86	1409.62	746.85	704.83	50.00	1383.06	1305.24
150+50.00	199.89	1354.01	235.38	1381.82	50.00	435.88	2558.92
151+00.00	49.44	1241.08	124.67	1297.55	50.00	230.86	2402.86
151+50.00	33.30	1063.28	41.37	1152.18	50.00	76.61	2133.67
152+00.00	27.20	883.39	30.25	973.34	50.00	56.02	1802.47
152+50.00	24.96	674.70	26.08	779.05	50.00	48.30	1442.68
153+00.00	18.25	465.28	21.61	569.99	50.00	40.01	1055.54
153+50.00	16.34	246.89	17.30	356.09	50.00	32.03	659.42
154+00.00	78.08	71.96	47.21	159.43	50.00	87.43	295.23
154+50.00	208.12	42.46	143.10	57.21	50.00	265.00	105.94
155+00.00	286.50	31.11	247.31	36.79	50.00	457.98	68.12
155+50.00	357.08	39.98	321.79	35.55	50.00	595.91	65.82
156+00.00	349.60	40.50	353.34	40.24	50.00	654.33	74.52
156+50.00	304.78	30.85	327.19	35.68	50.00	605.91	66.06
157+00.00	351.74	28.01	328.26	29.43	50.00	607.89	54.50
157+50.00	408.10	36.75	379.92	32.38	50.00	703.56	59.96
158+00.00	463.14	32.20	435.62	34.48	50.00	806.70	63.84
158+50.00	602.63	21.11	532.89	26.66	50.00	986.82	49.36
159+00.00	680.59	10.41	641.61	15.76	50.00	1188.17	29.19
159+50.00	1391.75	9.23	1036.17	9.82	50.00	1918.83	18.19
160+00.00	1325.69	1.75	1358.72	5.49	50.00	2516.15	10.17
160+50.00	1327.65	50.32	1326.67	26.04	50.00	2456.80	48.21
161+00.00	1122.97	32.09	1225.31	41.21	50.00	2269.09	76.31
161+50.00	1068.47	0.06	1095.72	16.08	50.00	2029.11	29.77
162+00.00	935.78	3.75	1002.13	1.91	50.00	1855.79	3.53
162+50.00	899.03	0.00	917.41	1.88	50.00	1698.90	3.47
163+00.00	1176.50	0.00	1037.77	0.00	50.00	1921.79	0.00
163+50.00	1097.95	0.00	1137.23	0.00	50.00	2105.97	0.00
164+00.00	1427.45	0.00	1262.70	0.00	50.00	2338.33	0.00
164+50.00	1327.98	0.00	1377.72	0.00	50.00	2551.32	0.00
165+00.00	1219.43	0.04	1273.71	0.02	50.00	2358.71	0.04
165+50.00	1482.19	0.04	1350.81	0.04	50.00	2501.50	0.07
166+00.00	713.16	75.50	1097.68	37.77	50.00	2032.73	69.94
166+50.00	525.11	78.26	619.14	76.88	50.00	1146.55	142.37
167+00.00	416.01	85.04	470.56	81.65	50.00	871.41	151.20
167+50.00	344.52	93.26	380.27	89.15	50.00	704.19	165.09
168+00.00	271.27	81.10	307.90	87.18	50.00	570.18	161.44
168+50.00	143.87	85.32	207.57	83.21	50.00	384.39	154.09
169+00.00	96.43	103.17	120.15	94.25	50.00	222.50	174.53
169+50.00	44.88	94.23	70.66	98.70	50.00	130.84	182.78
170+00.00	48.00	81.61	46.44	87.92	50.00	86.00	162.81

EARTH EXCAVATION ---- STEARNS ROAD

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)
170+50.00	69.58	83.64	58.79	82.63	50.00	108.87	153.01
171+00.00	84.46	101.30	77.02	92.47	50.00	142.63	171.24
171+50.00	46.56	128.05	65.51	114.68	50.00	121.31	212.36
172+00.00	29.31	173.42	37.94	150.74	50.00	70.25	279.14
172+50.00	25.77	224.35	27.54	198.89	50.00	51.00	368.31
173+00.00	23.93	244.89	24.85	234.62	50.00	46.02	434.48
173+50.00	20.61	246.35	22.27	245.62	50.00	41.24	454.85
174+00.00	16.97	244.70	18.79	245.53	50.00	34.80	454.68
174+50.00	22.06	241.39	19.52	243.05	50.00	36.14	450.08
175+00.00	24.78	265.77	23.42	253.58	50.00	43.37	469.59
175+50.00	20.77	275.58	22.78	270.68	50.00	42.18	501.25
176+00.00	34.66	231.32	27.72	253.45	50.00	51.32	469.35
176+50.00	38.82	148.04	36.74	189.68	50.00	68.04	351.26
177+00.00	43.19	126.43	41.01	137.24	50.00	75.94	254.14
177+50.00	50.21	141.23	46.70	133.83	50.00	86.48	247.83
178+00.00	45.47	114.30	47.84	127.77	50.00	88.59	236.60
178+50.00	35.94	158.75	40.71	136.53	50.00	75.38	252.82
179+00.00	37.44	148.20	36.69	153.48	50.00	67.94	284.21
179+50.00	43.03	159.83	40.24	154.02	50.00	74.51	285.21
180+00.00	53.73	155.79	48.38	157.81	50.00	89.59	292.24