
Contract # 63074



NOTES


Detail I - With Bar Splicer or Couplers: Connect one (1) 1"x7"x10" steel P to the top layer of couplers with $2 - \frac{5}{8}'' \phi$ bolts screwed to coupler at approximate @ of each barrier panel.

Detail II - With Extended Reinforcement Bars: Connect one (1) 1"x7"x10" steel P to the concrete slab or concrete wearing surface with 2^{-5}_8 " ϕ Expansion Anchors or cast in place inserts spaced between the top layer of reinforcement at approximate & of each barrier panel.


Cost of anchorage is included with Temporary Concrete Barrier. The 1" x 7" x 10" plate shall not be removed until stage II construction forms and all reinforcement bars are in place and the concrete is ready

SECTIONS THRU SLAB OR DECK BEAM


Dimension shown is minimum required embedment into concrete. If hot-mix asphalt wearing surface is present, minimum embedment shall be in addition to wearing surface depth. *If existing deck beam is to remain in place after stage construction. embedment shall only be into wearing surface and not into existing deck beam concrete.



DETAIL I



**Wood blocks may be omitted when required to provide minimum stage traffic lane width. When the wood blocks are omitted, the concrete barrier shall be in direct contact with the steel retainer plate.



STEEL RETAINER P 1" x 7" x 10"

* Required only with Detail II

DESIGNED AJKAAYCHECKED AYR DRAWN

DMC CHECKED R-27 9-3-07

when "A" is greater than 3'-6".

alfred benesch & company benesch

Engineers · Surveyors · Planners
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 66601
312-565-0450

FOR STAGE CONSTRUCTION IL 25/DUNHAM ROAD OVER THE EAST BRANCH OF BREWSTER CREEK F.A.P. 360 - SEC. 06-00214-15-BR KANE COUNTY STATION 276+36.96 STRUCTURE NO. 045-2032

TEMPORARY CONCRETE BARRIER