

REMOVAL SCHEDULE								
STATION		TREE REMOVAL (6 TO 15 UNITS DIAMETER) (UNITS)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNITS)	PAVEMENT REMOVAL (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL, 2" (SQ YD)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	PIPE CULVERT REMOVAL (FOOT)
		20100110	20100210	44000100	44000157	44000200	44000500	50105220
STEARNS RD	434+00 TO 447+00	114	261	5,610		575	222	167
	447+00 TO 460+00	204	144	5,265		620		106
	460+00 TO 473+00	222	19	679				
	473+00 TO 486+00	219	0	2,370				
	486+00 TO 499+00	104	0	4,366				
	499+00 TO 508+40	777	33	2,137				
RANDALL RD					8,578		80	
TOTAL		1,640	457	20,427	8,578	1,195	302	273

MEDIAN SCHEDULE						
STATION		COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (FOOT)	CONCRETE MEDIAN SURFACE, 4 INCH (SQ FT)	CONCRETE MEDIAN, TYPE SB-6.24 (SQ FT)	CONCRETE MEDIAN, TYPE SB-6.24 (MODIFIED) (SQ FT)	CORRUGATED MEDIAN (SQ FT)
		60608600	60618300	60620000	60620200	60624600
STEARNS RD	434+00 TO 447+00			261	2537	127
	447+00 TO 460+00			1,021	2506	200
	460+00 TO 473+00			0	0	0
	473+00 TO 486+00			487	960	97
	486+00 TO 499+00			0	0	0
	499+00 TO 508+40			261	2118	0
UMBENSTOCK RD		700+50 TO 702+50	18	162		
TOTAL		18	162	2,030	8121	424

PAVEMENT SCHEDULE													
STATION		PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) (SQ YD)	PORTLAND CEMENT CONCRETE SHOULDERS 6", SPECIAL (SQ YD)	AGGREGATE SHOULDERS, TYPE B 6" (SQ YD)	HOT-MIX ASPHALT SHOULDERS, 6" (SQ YD)	HMA ASPHALT PAVEMENT (FULL-DEPTH), 10 3/4" (SQ YD)	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE MIX F N90 2" (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (TON)	HMA BASE COURSE, 8" (SQ YD)	SUB-BASE GRANULAR MATERIAL TYPE B (TON)	AGGREGATE SUBGRADE 12" (SQ YD)	AGGREGATE BASE COURSE, TYPE B 6" (SQ YD)	CLASS D PATCHES, TYPE IV, 12 INCH
		42000501		48101500	48203021	40701896	40603595	40603310	35501316	31101000	Z0001050	35101800	44201796
STEARNS RD	434+00 TO 447+00	7734	404	101		2,458		30	264	32	12,104	271	387
	447+00 TO 460+00	10163	1967	555				21	163	103	13,257	160	136
	460+00 TO 473+00	7505	2090	590						90	10,774		
	473+00 TO 486+00	8401	1981	508						95	11,544		
	486+00 TO 499+00	7265	1924	441	106					172	10,525		
	499+00 TO 508+40	7368	810	199	298					25	9,315		
RANDALL RD		478+67 TO 487+80					961						
TOTAL		48436	9176	2,394	404	2,458	961	51	427	517	67,519	431	523

CURB AND GUTTER SCHEDULE						
STATION		CLASS SI CONCRETE OUTLET (CU YD)	CONCRETE GUTTER, TYPE A (FOOT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (FOOT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FOOT)	
		60600095	60602500	60603800	60605000	
					OUTER EDGE	MEDIAN
STEARNS RD	434+00 TO 447+00			73	1780	1135
	447+00 TO 460+00			96	292	1051
	460+00 TO 473+00				0	2600
	473+00 TO 486+00				256	1894
	486+00 TO 499+00	1.7			432	2600
	499+00 TO 508+40	2.1	946		946	1107
TOTAL		3.8	946	169	3706	10387

PRIME COAT SCHEDULE		
LOCATION	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	AGGREGATE (PRIME COAT) (TON)
	40600100	40600300
RANDALL RD RESURFACING	858	17
STEARNS RD RECONSTRUCTION	492	10
COMMERCIAL DRIVEWAYS	85	2
TOTAL	1435	29