

STEARNS ROAD SUPERELEVATION TABLE
CURVE #2

	WESTBOUND				EASTBOUND						
	STATION	MAINLINE LEFT E.O.P. (P.G.L.) ELEVATION	CROSS SLOPE %	MAINLINE LEFT E.O.P. ELEVATION (24' LT OF PGL)	MAINLINE RIGHT E.O.P. (P.G.L.) ELEVATION	CROSS SLOPE %	MAINLINE RIGHT E.O.P. ELEVATION (24' RT OF PGL)	RIGHT E.O.P. DISTANCE RIGHT OF E.O.P. (FT)	CROSS SLOPE %	RIGHT E.O.P. ELEVATION	STATION
	480+25.00	810.84	-2.00%	810.36	810.84	-2.00%	810.36				480+25.00
	480+50.00	810.71	-2.00%	810.23	810.71	-2.00%	810.23				480+50.00
BEGIN TANGENT RUNOUT	480+55.00	810.69	-2.00%	810.21	810.69	-2.00%	810.21				480+55.00
	480+75.00	810.59	-2.00%	810.11	810.59	-1.43%	810.25				480+75.00
	481+00.00	810.46	-2.00%	809.98	810.46	-0.71%	810.29				481+00.00
	481+25.00	810.34	-2.00%	809.86	810.34	0.00%	810.34				481+25.00
	481+50.00	810.21	-2.00%	809.73	810.21	0.74%	810.39				481+50.00
	481+75.00	810.09	-2.00%	809.61	810.09	1.48%	810.44				481+75.00
	482+00.00	809.96	-2.21%	809.43	809.96	2.21%	810.49				482+00.00
BEGIN FULL SUPERELEVATION	482+10.00	809.91	-2.51%	809.31	809.91	2.51%	810.51				482+10.00
	483+00.00	809.46	-2.51%	808.86	809.46	2.51%	810.06				483+00.00
	484+00.00	808.96	-2.51%	808.36	808.96	2.51%	809.56				484+00.00
	485+00.00	808.46	-2.51%	807.86	808.46	2.51%	809.06				485+00.00
	486+00.00	807.61	-2.51%	807.01	807.61	2.51%	808.21				486+00.00
	487+00.00	805.67	-2.51%	805.07	805.67	2.51%	806.27				487+00.00
	488+00.00	802.64	-2.51%	802.04	802.64	2.51%	803.24				488+00.00
	489+00.00	798.85	-2.51%	798.25	798.85	2.51%	799.45				489+00.00
	490+00.00	795.04	-2.51%	794.44	795.04	2.51%	795.64				490+00.00
	491+00.00	791.23	-2.51%	790.63	791.23	2.51%	791.83				491+00.00
	492+00.00	787.42	-2.51%	786.82	787.42	2.51%	788.02				492+00.00
	493+00.00	783.61	-2.51%	783.01	783.61	2.51%	784.21	-	-	-	493+00.00
	494+00.00	779.80	-2.51%	779.20	779.80	2.51%	780.41	-	-	-	494+00.00
	495+00.00	775.99	-2.51%	775.39	775.99	2.51%	776.59	-	-	-	495+00.00
	496+00.00	772.19	-2.51%	771.58	772.19	2.51%	772.79	-	-	-	496+00.00
	497+00.00	768.38	-2.51%	767.78	768.38	2.51%	768.98	-	-	-	497+00.00
	498+00.00	764.57	-2.51%	763.97	764.57	2.51%	765.17	-	-	-	498+00.00
	499+00.00	760.76	-2.51%	760.16	760.76	2.51%	761.36	4.00	-4.00%	761.20	499+00.00
	500+00.00	756.95	-2.51%	756.35	756.95	2.51%	757.55	4.00	-4.00%	757.39	500+00.00
END FULL SUPERELEVATION	501+00.00	753.14	-2.51%	752.54	753.14	2.51%	753.74	4.00	-4.00%	753.58	501+00.00
	501+25.00	752.19	-2.36%	751.62	752.19	1.77%	752.62	-	-	-	501+25.00
	501+50.00	751.24	-2.21%	750.71	751.24	1.03%	751.48	4.00	-4.00%	751.32	501+50.00
	501+75.00	750.28	-2.06%	749.79	750.28	0.30%	750.35	-	-	-	501+75.00
END SUPERELEVATION RUNOFF	501+85.00	749.91	-2.00%	749.43	749.91	0.00%	749.91	-	-	-	501+85.00
	502+00.00	749.33	-2.00%	748.85	749.33	-0.43%	749.23	4.00	-4.00%	749.07	502+00.00
	502+25.00	748.38	-2.00%	747.90	748.38	-1.14%	748.11	-	-	-	502+25.00
	502+50.00	747.43	-2.00%	746.95	747.43	-1.86%	746.98	-	-	-	502+50.00
END TANGENT RUNOUT	502+55.00	747.24	-2.00%	746.76	747.24	-2.00%	746.76	-	-	-	502+55.00
	502+75.00	746.48	-2.00%	746.00	746.48	-2.00%	746.00	-	-	-	502+75.00