

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y031-IF	100% DEERFIELD
20101000	TEMPORARY FENCE	FOOT	1120	1120		
20101200	TREE ROOT PRUNING (SPECIAL)	EACH	15	15		
20101300	TREE PRUNING 1-10	EACH	7	7		
20101350	TREE PRUNING OVER 10	EACH	5	5		
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	14	14		
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	14	14		
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	14	14		
20200100	EARTH EXCAVATION	CU YD	1400	1400		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	130	130		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	130	130		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	390	390		
21101615	TOPSOIL FURISH AND PLACE, 4"	SQ YD	1080	1080		
25200110	SODDING, SALT TOLERANT	SQ YD	1080	1080		
25200200	SUPPLEMENTAL WATERING	UNIT	6	6		
28000510	INLET FILTERS	EACH	55	55		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	5320	5197		123
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	300	300		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1910	1910		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	3180	3180		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	3910	3910		
40600300	AGGREGATE (PRIME COAT)	TON	80	80		
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	1100	1100		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	245	245		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1750	1750		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5"	SQ FT	8000	7220		780
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6"	SQ FT	130	130		
42400800	DETECTABLE WARNINGS	SQ FT	500	500		
44000100	PAVEMENT REMOVAL	SQ YD	140	140		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	17300	17300		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	825	825		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4190	4075		115
44000600	SIDEWALK REMOVAL	SQ FT	8130	6295		1835
60603800	COMBINATION CURB AND GUTTER TYPE B-6.12	FOOT	5310	5194		116
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		
67100100	MOBILIZATION	L SUM	1	1		
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1		
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4370	4370		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9500	9500		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	30	30		
72000100	SIGN PANEL - TYPE 1	SQ FT	104	104		
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	18	18		
72900200	METAL POST - TYPE B	FOOT	236	236		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	801	801		

* SPECIALTY ITEM

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y031-IF	100% DEERFIELD
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6360	6360		
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3430	3430		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	205	205		
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	255	255		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	60	60		
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1		
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	25	25		
81000700	CONDUIT TRENCHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	80	80		
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	14	14		
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	35	35		
81400100	HANDHOLE	EACH	2	2		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	102	102		
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1		
85700100	FULL-ACTUATED CONTROLLER AND TYPE III CABINET	EACH	1	1		
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1	1		
87301215	ELECTRIC CABLE IN CONDUIT SIGNAL 14 2C	FOOT	140	140		
87301225	ELECTRIC CABLE IN CONDUIT SIGNAL 14 3C	FOOT	160	160		
87301245	ELECTRIC CABLE IN CONDUIT SIGNAL 14 5C	FOOT	480	480		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO.6 2C	FOOT	30	30		
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO.6 1C	FOOT	170	170		
87502460	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 12 FT	EACH	2	2		
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2	2		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8		
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4		
87800400	CONCRETE FOUNDATION, TYPE E, 30" DIAMETER	FOOT	30	30		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	4		
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2		
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	4	4		
88800100	PEDESTRIAN PUSH BUTTON	EACH	2	2		
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1		
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1		
89502380	REMOVE EXISTING HANDHOLE	EACH	2	2		
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	5	5		
XX003338	TEST HOLE	EACH	10	5		5
XX007490	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	265	265		
XX004904	BITUMINOUS DRIVEWAY PAVEMENT 10"	SQ YD	430	430		
20013798	CONSTRUCTION LAYOUT	L SUM	1	1		
X0301766	DRILL AND GROUT #6 TIE BARS	EACH	633	633		
XX002258	STRUCTURES TO BE ADJUSTED	EACH	20	20		
20076600	TRAINERS	HOUR	500	500		
XX004689	SANITARY SERVICE TO BE ADJUSTED	EACH	25			25
20800150	TRENCH BACKFILL	CU YD	4048	320		3728
X0712400	TEMPORARY PAVEMENT	SQ YD	380			380
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	110	110		
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	230	230		

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A	Y031-IF	100% DEERFIELD
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	620	620		
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	3530	3530		
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	70	70		
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	120	120		
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	70	70		
55100500	STORM SEWER REMOVAL, 12"	FOOT	645	645		
55100900	STORM SEWER REMOVAL, 18"	FOOT	85	85		
55101200	STORM SEWER REMOVAL, 24"	FOOT	75	75		
60200105	CATCH BASINS, TYPE A, 4'-DIAMETER TYPE 1 FRAME, OPEN LID	EACH	24	24		
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6		
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2		
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8	8		
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	17	17		
60500040	REMOVING MANHOLES	EACH	11	11		
60500050	REMOVING CATCH BASINS	EACH	27	27		
60500060	REMOVING INLETS	EACH	24	24		
60500070	REMOVING MANHOLES TO MAINTAIN FLOW	EACH	1	1		
X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	320	320		
X0321907	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 12"	FOOT	225	225		
X0321909	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	75	75		
60206905	CATCH BASINS, TYPE C, 2'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	12	12		
X0321914	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 18"	FOOT	35	35		
20041700	PLUG EXISTING STORM SEWERS	EACH	2	2		
XX002136	PRESSURE CONNECTION	EACH	1			1
56103000	DUCTILE IRON WATER MAIN, 6"	FOOT	165			165
56103100	DUCTILE IRON WATER MAIN, 8"	FOOT	560			560
56103200	DUCTILE IRON WATER MAIN, 10"	FOOT	4460			4460
56104900	WATER VALVES, 6"	EACH	3			3
56105000	WATER VALVES, 8"	EACH	9			9
56105100	WATER VALVES, 10"	EACH	8			8
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	12			12
60249120	VALVE VAULTS, 5'-DIAMETER	EACH	18			18
60249400	VALVE BOXES, 6"	EACH	2			2
60500370	FILLING VALVE BOXES	EACH	1			1
60500405	FILLING VALVE VAULTS	EACH	12			12
60500505	FILLING METER VAULTS	EACH	1			1
X0300020	WATER SERVICE CONNECTION	EACH	38			38
X0325012	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 10"	EACH	1			1
X5640150	FIRE HYDRANT ASSEMBLY COMPLETE	EACH	12			12
XX003516	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 8"	EACH	9			9
XX003517	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 6"	EACH	1			1
XX005107	CONNECTIONS TO EXISTING WATER MAINS (NON-PRESSURE) - 12"	EACH	1			1
X0321914	Cut and Cap Existing Water Main	EACH	9			9
XX007871	STORM SEWER SERVICE, 6" (SHORT) (TYP.)	EACH	25	25		
XX007874	STORM SEWER SERVICE, 6" (LONG) (TYP.)	EACH	12	12		

FILE NAME = N:\PROJ\3328\Phase II\Design\MiscSheets\3328-S00.dgn	USER NAME = cgurowaki	DESIGNED - EPS	REVISED -	VILLAGE OF DEERFIELD WILMOT ROAD (GORDON TERRACE TO DEERFIELD ROAD)	SUMMARY OF QUANTITIES	F.A.U. R.T.E. 2718	SECTION 07-00080-00-WR	COUNTY LAKE	TOTAL SHEETS 55	SHEET NO. 3			
	PLOT SCALE = 2.0004' / IN.	DRAWN - AL	REVISED -			SCALE:	SHEET NO. 3 OF 55 SHEETS	STA.	TO STA.	CONTRACT NO. 63124			
	PLOT DATE = 5/13/2009	CHECKED - CLG	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
		DATE - 4-7-2009	REVISED -										