

SPECIALTY ITEM	CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	
					STP	80% FED / 20% VILLAGE
					1000-2A	
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	274	274	
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7,555	7,555	
	20400800	FURNISHED EXCAVATION	CU YD	1,180	1,180	
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	745	745	
	20800150	TRENCH BACKFILL	CU YD	500	500	
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	9,900	9,900	
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	50	50	
*	25000210	SEEDING, CLASS 2A	ACRE	2.0	2.0	
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	185	185	
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	185	185	
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	185	185	
*	25100630	EROSION CONTROL BLANKET	SQ YD	9,000	9,000	
*	25300910	SALVAGING AND TRANSPLANTING TREES, SPECIAL	EACH	10	10	
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
	28000300	TEMPORARY DITCH CHECK	EACH	12	12	
	28000400	PERIMETER EROSION BARRIER	FOOT	700	700	
	28000500	INLET AND PIPE PROTECTION	EACH	1	1	
	28000510	INLET FILTERS	EACH	22	22	
	28100107	STONE RIPRAP, CLASS A4	SQ YD	36	36	
	31101200	SUB-BASE GRANULAR MATERIAL, TYPE B, 4"	SQ YD	12,825	12,825	
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	536	536	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	1,215	1,215	
	40600300	AGGREGATE (PRIME COAT)	TON	24	24	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL, BUTT-JOINT	SQ YD	375	375	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	233	233	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	227	227	
	40701881	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 10"	SQ YD	10,125	10,125	
	42001300	PROTECTIVE COAT	SQ YD	536	536	
	42400800	DETECTABLE WARNINGS	SQ FT	116	116	
	44000100	PAVEMENT REMOVAL	SQ YD	9,696	9,696	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1,490	1,490	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	280	280	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	220	220	
	44000600	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	4,395	4,395	
	44004700	SIDEWALK REMOVAL	SQ FT	679	679	
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	110	110	
	48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	2,012	2,012	
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	1,679	1,679	
	50105220	PIPE CULVERT REMOVAL	FOOT	100	100	
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	
	54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1	
	55100500	STORM SEWER REMOVAL 12"	FOOT	179	179	
	55100700	STORM SEWER REMOVAL 15"	FOOT	219	219	
	60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	8	8	

SPECIALTY ITEM	CODE NO	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY	
					STP	80% FED / 20% VILLAGE
					1000-2A	
	60203805	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1	
	60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	7	7	
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3	
	60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4	
	60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	1	1	
	60600095	CLASS SI CONCRETE (OUTLET)	CU YD	6	6	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	269	269	
	67100100	MOBILIZATION	L SUM	1	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	600	600	
	72000100	SIGN PANEL - TYPE 1	SQ FT	145	145	
	72900100	METAL POST - TYPE A	FOOT	351	351	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	180	180	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14,910	14,910	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,100	1,100	
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	135	135	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,102	1,102	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	95	95	
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	175	175	
	550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	421	421	
	550A0360	STORM SEWERS, CLASS A, TYPE 2, 15"	FOOT	123	123	
	550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	695	695	
	550A0410	STORM SEWERS, CLASS A, TYPE 2, 24"	FOOT	239	239	
	550A0430	STORM SEWERS, CLASS A, TYPE 2, 30"	FOOT	135	135	
	550A0450	STORM SEWERS, CLASS A, TYPE 2, 36"	FOOT	857	857	
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	100	100	
	X0325416	TRAFFIC CONTROL AND PROTECTION FOR DETOUR ROUTE	L SUM	1	1	
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1	1	
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2	
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	3	3	
*	XX006570	TREES (SPECIAL)	EACH	20	20	
	XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	205	205	
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
	Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	1	1	
	Z0018700	DRAINAGE STRUCTURES TO BE REMOVED	EACH	8	8	
	Z0076600	TRAINEES	HOURS	500	500	
	XX007026	FENCE REMOVAL AND REINSTALLATION	FOOT	580	580	
	00325796	GATES TO BE REMOVED AND RE-ERECTED	EACH	1	1	

Δ = 9080

COMPANY NAME: Smith  
PROJECT CONTACT: #PROJECT CONTACT  
CLIENT: #CLIENT  
DATE PLOTTED: 4/1/2009 4:15:18 PM  
FILE NAME: 07070-sum.dgn  
PLOT DRIVER: pdfcut  
PLOT TABLE: standard-trans.tbl



USER NAME = charlke	DESIGNED - JLP	REVISED
FILE NAME = 07070-sum.dgn	DRAWN - BDH	REVISED
PLOT SCALE = NTS	CHECKED - DVC	REVISED
PLOT DATE = 4/1/2009	DATE - 4/1/09	REVISED

**VILLAGE OF LAKE IN THE HILLS**

SUMMARY OF QUANTITIES	
SCALE: NTS	SHEET NO. 1 OF 1 SHEETS
STA.	TO STA.

F.A. RTE. 3869	SECTION 08-00030-00-FP	COUNTY MCHENRY	TOTAL SHEETS 32	SHEET NO. 3
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT				

**CONTRACT NO. 63146**