


**SUMMARY OF QUANTITIES**

CODE NUMBER	PAY ITEM DESCRIPTION	UNITS	ROADWAY 1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,055
40600300	AGGREGATE (PRIME COAT)	TON	45
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,830
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,870
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	525
42400800	DETECTABLE WARNINGS	SQ FT	120
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4 INCH	SQ YD	21,580
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	525
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	5,830
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	585
60251500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	2
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	8
60261300	INLETS TO BE ADJUSTED WITH NEW TYPE 11 FRAME AND GRATE	EACH	9
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3
67100100	MOBILIZATION	LSUM	1
70106810	CHANGEABLE MESSAGE SIGN, SPECIAL	CAL MO	2
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,225
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	240
70300520	PAVEMENT MARKING TAPE, TYPE III - 4 INCH	FOOT	800
70300540	PAVEMENT MARKING TAPE, TYPE III - 6 INCH	FOOT	40
70300560	PAVEMENT MARKING TAPE, TYPE III - 12 INCH	FOOT	280
70300570	PAVEMENT MARKING TAPE, TYPE III - 24 INCH	FOOT	70
* 78000100	THERMOPLASTIC PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	280
* 78000200	THERMOPLASTIC PAVEMENT MARKING, LINE 4 INCH	FOOT	9,880
* 78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6 INCH	FOOT	650
* 78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12 INCH	FOOT	280
* 78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24 INCH	FOOT	130
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	800
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	20
X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	500
XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	30

\* SPECIALTY ITEMS

 <b>SEC Group, Inc.</b> <small>Engineering Surveying Planning Landscape Architecture</small> <small>McHenry • Yorkville • New Lenox • Chicago</small> <small>www.secgroupinc.com</small>	USER NAME = jstrzelka PLOT SCALE = NONE PLOT DATE = 2/16/2009	DESIGNED - JJS DRAWN - JJS CHECKED - AC DATE - 2/16/09	REVISED - REVISED - REVISED - REVISED -	<b>CITY OF AURORA</b>	<b>SUMMARY OF QUANTITIES</b>	F.A. RTE. 0360 SECTION 08-00279-00-RS COUNTY KANE TOTAL SHEETS 12 SHEET NO. 3	CONTRACT NO. 63155 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
	SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. NA TO STA. NA						