

SCHEDULE OF QUANTITIES

20100500	TREE REMOVAL, ACRES							
	<u>ACRES</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	0.19	LT/RT	995 + 11	TO	997 + 82			
	0.19	TOTAL						

20300100	CHANNEL EXCAVATION							
	<u>CU_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	109	RT. STA.	995 + 38	TO	996 + 2			
	109	TOTAL						

25100630	EROSION CONTROL BLANKET							
	<u>SD_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	125	RT. STA.	994 + 51	TO	995 + 31			
	263	RT. STA.	996 + 67	TO	997 + 77			
	388	TOTAL						

28000300	TEMPORARY DITCH CHECKS							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	1	LT. STA.	994 + 92					
	1	TOTAL						

28000400	PERIMETER EROSION BARRIER							
	<u>FOOT</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	88.0	LT. STA.	995 + 75	TO	996 + 60			
	54	LT. STA.	997 + 34	TO	997 + 88			
	142	TOTAL						

28000500	INLET AND PIPE PROTECTION							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	1	LT. STA.	994 + 9					
	1	LT. STA.	995 + 31					
	1	RT. STA.	994 + 80					
	1	RT. STA.	997 + 4					
	4	TOTAL						

28100107	STONE RIPRAP, CLASS A4							
	<u>SD_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	130.4	RT. STA.	995 + 22	TO	996 + 7	South Channel slopes		
	94.2	RT. STA.	996 + 50	TO	997 + 23	North Channel slopes		
	225	TOTAL						

28200200	FILTER FABRIC							
	<u>SD_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	130.4	RT. STA.	995 + 22	TO	996 + 7	South Channel slopes		
	94.2	RT. STA.	996 + 50	TO	997 + 23	North Channel slopes		
	225	TOTAL						

44201359	CLASS C PATCHES, TYPE IV, 10 INCH							
	<u>SD_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	399	RT. STA.	995 + 64	TO	997 + 2	Culvert at Sta. 996+33.55		
	399	TOTAL						

50100300	REMOVAL OF EXISTING STRUCTURES NO.1							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	1	LT/RT	996 + 33			Double 7x7 Concrete Box Culvert		
	1	TOTAL						

50200400	ROCK EXCAVATION FOR STRUCTURES							
	<u>CU_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	113	LT/RT	996 + 33			Double 7x7 Concrete Box Culvert		
	113	TOTAL						

50800105	REINFORCEMENT BARS							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	47260		996 + 33			Double 7x7 Concrete Box Culvert		
	47260	TOTAL						

50800205	REINFORCEMENT BARS, EPOXY COATED							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	630		996 + 33			Double 7x7 Concrete Box Culvert		
	630	TOTAL						

50800515	BAR SPLICERS							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	88		996 + 33			Double 7x7 Concrete Box Culvert		
	88	TOTAL						

51500100	NAME PLATES							
	<u>EACH</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	1	LT/RT	996 + 33			Double 7x7 Concrete Box Culvert		
	1	TOTAL						

54003000	CONCRETE BOX CULVERTS							
	<u>CU_YD</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	215.2		996 + 33			Double 7x7 Concrete Box Culvert		
	215.2	TOTAL						

54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"							
	<u>FOOT</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	42	RT	994 + 9	TO	994 + 51	PE - Pipe set at 29.5' LT		
	42	TOTAL						

54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"							
	<u>FOOT</u>	<u>LOCATION</u>					<u>REMARKS</u>	
	116	RT	994 + 80	TO	995 + 96	FE - Pipe set at 28' RT		
	94	RT	996 + 10	TO	997 + 4	PE - pipe set at 33' RT		
	210	TOTAL						

FILE NAME =	USER NAME = hensonke	DESIGNED -	REVISED -
c:\pw\work\FWIDOT\HENSONKE\dms34329\dms34329.dwg		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	103MFT-T	ROCK ISLAND	55	10
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 64737				