

# SCHEDULE OF QUANTITIES

20101400      **NITROGEN FERTILIZER NUTRIENT**

POUND	LOCATION				
36	LT & RT Sta.	1171+50.0	TO	1176+00.0	
36	LT & RT Sta.	1199+50.0	TO	1203+50.0	
28	LT & RT Sta.	1281+50.0	TO	1285+50.0	
100	TOTAL				

Note: 90 pounds fertilizer nutrient per acre.  
Quantities rounded up to the nearest 100 lb per bag

25000310      **SEEDING, CLASS 4**

ACRE	LOCATION				
0.2	LT & RT Sta.	1171+50.0	TO	1176+00.0	
0.1	LT & RT Sta.	1199+50.0	TO	1203+50.0	
0.1	LT & RT Sta.	1281+50.0	TO	1285+50.0	
0.4	TOTAL				

20101500      **PHOSPHORUS FERTILIZER NUTRIENT**

POUND	LOCATION				
36	LT & RT Sta.	1171+50.0	TO	1176+00.0	
36	LT & RT Sta.	1199+50.0	TO	1203+50.0	
28	LT & RT Sta.	1281+50.0	TO	1285+50.0	
100	TOTAL				

Note: 90 pounds fertilizer nutrient per acre.  
Quantities rounded up to the nearest 100 lb per bag

25100115      **MULCH, METHOD 2**

ACRE	LOCATION				
0.4	LT & RT Sta.	1171+50.0	TO	1176+00.0	
0.3	LT & RT Sta.	1199+50.0	TO	1203+50.0	
0.4	LT & RT Sta.	1281+50.0	TO	1285+50.0	
1.0	TOTAL				

20101600      **POTASSIUM FERTILIZER NUTRIENT**

POUND	LOCATION				
36	LT & RT Sta.	1171+50.0	TO	1176+00.0	
36	LT & RT Sta.	1199+50.0	TO	1203+50.0	
28	LT & RT Sta.	1281+50.0	TO	1285+50.0	
100	TOTAL				

Note: 90 pounds fertilizer nutrient per acre.  
Quantities rounded up to the nearest 100 lb per bag

25100630      **EROSION CONTROL BLANKET**

SQ YD	LOCATION				
163	LT Sta.	1173+57.0	TO	1176+00.0	
202	RT Sta.	1172+50.0	TO	1176+00.0	
285	LT Sta.	1199+50.0	TO	1203+50.0	
285	RT Sta.	1199+50.0	TO	1203+50.0	
115	LT Sta.	1282+00.0	TO	1283+50.0	
276	RT Sta.	1281+50.0	TO	1285+25.0	
1326	TOTAL				

see R.O.W , Erosion control & Seeding sheets for spacing and offsets.

20200100      **EARTH EXCAVATION**

CU YD	LOCATION				
430	LT & RT Sta.	1171+50.0	TO	1176+00.0	
365	LT & RT Sta.	1199+50.0	TO	1203+50.0	
135	LT & RT Sta.	1281+50.0	TO	1285+50.0	
930	TOTAL				

28000250      **TEMPORARY EROSION CONTROL SEEDING**

POUND	LOCATION	
921	Entire Job	

\*Based on 7 Calendar days per Location, 100 pound/acre.

21101615      **TOPSOIL FURNISH AND PLACE, 4"**

SQ YD	LOCATION				
1500	LT & RT Sta.	1171+50.0	TO	1176+00.0	
1549	LT & RT Sta.	1199+50.0	TO	1203+50.0	
1355	LT & RT Sta.	1281+50.0	TO	1285+50.0	
4404	TOTAL				

28000300      **TEMPORARY DITCH CHECKS**

EACH	LOCATION				
5	LT Sta.	1174+00.0	TO	1176+00.0	
7	RT Sta.	1172+50.0	TO	1176+00.0	
7	LT Sta.	1199+50.0	TO	1203+50.0	
12	RT Sta.	1199+50.0	TO	1203+50.0	
6	LT Sta.	1282+00.0	TO	1283+50.0	
6	RT Sta.	1281+50.0	TO	1285+00.0	
43	TOTAL				

Noteseee R.O.W , Erosion control & Seeding sheets for spacing and offsets.

25000210      **SEEDING, CLASS 2A**

ACRE	LOCATION				
0.2	LT & RT Sta.	1171+50.0	TO	1176+00.0	
0.2	LT & RT Sta.	1199+50.0	TO	1203+50.0	
0.2	LT & RT Sta.	1281+50.0	TO	1285+50.0	
0.6	TOTAL				