

BRF

← NHF →

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE X071-2A TOTAL QUANTITY	50% STATE 50% CITY X071-2A TOTAL QUANTITY	80% FED 20% STATE SFTY-2A TOTAL QUANTITY	80% FED 20% STATE J000 TOTAL QUANTITY	80% FED 20% STATE Y044 TOTAL QUANTITY	75% STATE 25% CITY Y044 TOTAL QUANTITY	100% CITY SFTY-2A TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	132				132			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1231				1231			
20200100	EARTH EXCAVATION	CU YD	4760				4760			
20300100	CHANNEL EXCAVATION	CU YD	4624	4624						
20400800	FURNISHED EXCAVATION	CU YD	3395				3395			
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	155	155						
20800150	TRENCH BACKFILL	CU YD	1009				1009			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	5659				5659			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2844				2844			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	35.0				35			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	35.0				35			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	35.0				35			
25200100	SODDING	SQ YD	2844				2844			
25200200	SUPPLEMENTAL WATERING	UNIT	87				87			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2400				2400			
28000400	PERIMETER EROSION BARRIER	FOOT	631				631			
28000500	INLET AND PIPE PROTECTION	EACH	2				2			
28200200	FILTER FABRIC	SQ YD	2415	2415						
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	2415	2415						
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	2825				2825			
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	733				733			
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SQ YD	1002				1002			
31100975	SUB-BASE GRANULAR MATERIAL, TYPE A 30"	SQ YD	1099				1099			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	2115				2115			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1290				1290			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.0				4			
40603340	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	15			15				
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	390				390			
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SQ YD	4541				4541			
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	356	356						
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	1395				1395			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	18711					1659	17052	
42400800	DETECTABLE WARNINGS	SQ FT	40					40		
44000100	PAVEMENT REMOVAL	SQ YD	4019				4019			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3189				3189			
44000400	GUTTER REMOVAL	FOOT	1691				1691			
44000600	SIDEWALK REMOVAL	SQ FT	1490				1490			
44001005	HOT - MIX ASPHALT SURFACE REMOVAL	SQ YD	16			16				
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	158				158			
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	SQ YD	428				428			

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = jordanhd	DESIGNED -	REVISED -
ct\p\work\FWIDOT\JORDANHD\dms34552\st130850v.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Mon Mar 16 11:21:09 2009		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

----- SUMMARY OF QUANTITIES -----

SCALE: \_\_\_\_\_ SHEET NO. \_\_\_ OF \_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	UTBR	WHITESIDE	376	3
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64B74	