

BRF

NHF

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	BRF		NHF					
				80% FED 20% STATE X071-2A TOTAL QUANTITY	50% STATE 50% CITY X071-2A TOTAL QUANTITY	80% FED 20% STATE SFTY-2A TOTAL QUANTITY	80% FED 20% STATE J000 TOTAL QUANTITY	80% FED 20% STATE Y044 TOTAL QUANTITY	75% STATE 25% CITY Y044 TOTAL QUANTITY	100% CITY SFTY-2A TOTAL QUANTITY	
58300100	PORTLAND CEMENT MORTAR FAIRING COURSE	FOOT	210			210					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	95	95							
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	146	146							
60107600	PIPE UNDERDRAINS 4"	FOOT	227				227				
60218400	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3				3				
60224445	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2				2				
60242400	INLETS, SPECIAL	EACH	2				2				
60242801	INLETS, SPECIAL, NO. 5	EACH	14				14				
60242803	INLETS, SPECIAL, NO. 7	EACH	1				1				
60242804	INLETS, SPECIAL, NO. 8	EACH	6				6				
60255500	MANHOLES TO BE ADJUSTED	EACH	2								2
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2								2
60266600	VALVE BOXES TO BE ADJUSTED	EACH	10								10
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2722				2722				
63200310	GUARDRAIL REMOVAL	FOOT	381				381				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16				16				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2				2				
67100100	MOBILIZATION	L SUM	1				1				
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	7				7				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1				1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1				1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1				1				
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1				1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10				10				
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	12291				12291				
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	131				131				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3624				3624				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1575				1575				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2775				2775				
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	6107				6107				
78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	118				118				
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	18				18				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	28				28				
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1				1				
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1				1				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1				1				
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	8				8				
Z0030030	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4				4				
Z0030250	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2								
Z0030280	IMPACT ATTENUATORS TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3	EACH	2								
Z0030350	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	12								
Z0030360	IMPACT ATTENUATORS RELOCATE (SEVERE USE), TEST LEVEL 3	EACH	2								

* SPECIALTY ITEMS

FILE NAME = c:\pwork\pwork\JORDANHD\dms34552\13985covr.dgn	USER NAME = Jordanhd	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE. 309	SECTION (17)R	COUNTY WHITESIDE	TOTAL SHEETS 376	SHEET NO. 5
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	SCALE: _____		SHEET NO. ___ OF ___ SHEETS			CONTRACT NO. 64B74				
PLOT DATE = Mon Mar 16 08:27:03 2009	DATE -	REVISED -	STA. _____ TO STA. _____			ILLINOIS FED. AID PROJECT						