

6022446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, OPEN LID LOCATION STA. 1039+20.37 STA. 1042+42.65	RT RT TOTAL =	EACH 1 1 2	REMARKS 36.60' RT 35.38' RT
60242400	INLETS, SPECIAL LOCATION STA. 1041+03.08 STA. 1041+13.46	LT LT TOTAL =	EACH 1 1 2	REMARKS 48.31' 48.45'
60242801	INLETS, SPECIAL, NO. 5 LOCATION STA. 1031+39.45 STA. 1033+86.48 STA. 1033+86.53 STA. 1036+36.50 STA. 1036+36.77 STA. 1040+01.43 STA. 1041+75.16 STA. 1042+46.00 STA. 1043+77.00 STA. 1044+37.84 STA. 1044+83.96 STA. 1044+86.88 STA. 1045+40.39 STA. 1046+50.19	RT LT RT RT LT LT LT LT LT LT LT LT LT LT TOTAL =	EACH 1 1 1 1 1 1 1 1 1 1 1 1 1 1 14	REMARKS 17.00' 15.83' 23.75' 23.75' 14.40' 9.75' 14.60' 16.68' 16.75' 53.43' 54.01' 47.43' 16.75' 15.81'
60242803	INLETS, SPECIAL, NO. 7 LOCATION STA. 1043+77.00	RT TOTAL =	EACH 1 1	REMARKS
60242804	INLETS, SPECIAL, NO. 8 LOCATION STA. 1040+01.40 STA. 1041+51.64 STA. 1042+44.04 STA. 1044+00.18 STA. 1045+40.80 STA. 1046+50.62	RT RT RT RT RT RT TOTAL =	EACH 1 1 1 1 1 1 6	REMARKS 24.75' 20.62' 17.88'
60255500	MANHOLES TO BE ADJUSTED LOCATION STA. 1035+25 STA. 1045+00	RT RT TOTAL =	EACH 1 1 2	REMARKS
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID LOCATION THROUGHOUT PROJECT	TOTAL =	EACH 2 2	REMARKS
60266600	VALVE BOXES TO BE ADJUSTED LOCATION THROUGHOUT PROJECT	TOTAL =	EACH 10 10	REMARKS
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24 LOCATION STA 1031+16.61 TO STA 1036+87.27 STA 1031+30.05 TO STA 1036+87.27 STA 1038+82.27 TO STA 1046+62.00 STA 1038+82.27 TO STA 1044+40.25 STA 1044+79.90 TO STA 1046+62.00	RT LT RT LT LT TOTAL =	FOOT 570.66 557.22 769.85 609.60 214.56 2721.9	REMARKS
63200310	GUARDRAIL REMOVAL LOCATION RT STA 1036+92.48 TO 1037+10.03 LT STA 1036+98.27 TO 1037+10.46 RT STA 1038+16.37 TO 1039+20.02 LT STA 1038+16.53 TO 1039+20.69 RT STA 1042+11.86 TO 1043+02.57 R 2	FOOT 32.00 43.00 103.65 103.65 98.65 TOTAL =	REMARKS RADIUS FOR ENTRANCE RADIUS FOR ENTRANCE OVER TRIPLE BOX CULVERT	381

66700305	PERMANENT SURVEY MARKERS, TYPE II LOCATION SEE GENERAL NOTES	EACH 2 TOTAL =	REMARKS
70106500	TEMPORARY BRIDGE SIGNALS LOCATION PRE-STAGE 2	EACH 1.00 TOTAL =	REMARKS SEE STAGING PLANS FOR LOCATIONS
70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4" LOCATION PRE-STAGE 1 STA 1029+08.39 TO 1036+87.27 STA 1038+82.27 TO 1048+06.80 PRE-STAGE 2 STA 1035+12.90 TO 1041+04.97 PRE-STAGE 3 STA 1034+37.55 TO 1041+00.80 PRE-STAGE 4 STA 1039+56.78 TO 1046+76.72 STA 1040+40.13 TO 1045+76.37 PRE-STAGE 5 STA 1040+06.78 TO 1045+26.74 STAGE 1 STA 1033+07.54 TO 1042+69.08 STA 1034+21.66 TO 1042+07.88 STAGE 2 STA 1027+61.90 TO 1042+00.73 STA 1029+21.55 TO 1048+06.80 STAGE 3 STA 1035+87.49 TO 1049+69.09 STA 1036+87.27 TO 1048+06.68	FOOT 778.38 874.42 593.56 682.51 723.87 536.64 520.82 962.93 789.22 1441.20 1884.29 1384.83 1118.30 TOTAL =	REMARKS
70300660	TEMPORARY PAINT PAVEMENT MARKING - LINE 24" LOCATION PRE-STAGE 2 STA 1034+27.62 STA 1041+75.80 PRE-STAGE 4 STA 1039+56.78 STA 1047+36.56 STAGE 1 STA 1032+38.56 STA 1042+64.22 STAGE 2 STA 1027+62.75 STA 1042+62.24 STAGE 3 STA 1035+75.50 STA 1050+29.09	FOOT 11.80 12.30 13.40 13.20 10.20 13.00 11.90 21.00 12.00 11.80 TOTAL =	REMARKS