

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3
 LOCATION EACH REMARKS
 PRE-STAGE 2
 STA 1036+37 LT 1
 STA 1039+37 LT 1
 TOTAL = 2

Z0030280 IMPACT ATTENUATORS, TEMPORARY (SEVERE USE, NARROW), TEST LEVEL 3
 LOCATION EACH REMARKS
 STAGE 2
 STA 1036+68 LT 1
 STA 1038+94 LT 1
 TOTAL = 2

Z0030350 IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
 LOCATION EACH REMARKS
 PRE-STAGE 3
 STA 1036+37 TO STA 1036+00 RT 1
 STA 1039+37 TO STA 1039+74 RT 1
 PRE-STAGE 4
 STA 1036+00 TO STA 1040+74 RT 1
 STA 1039+74 TO STA 1045+00 RT 1
 PRE-STAGE 5
 STA 1040+74 TO STA 1041+34 LT 1
 STA 1045+00 TO STA 1043+47 LT 1
 STAGE 1
 STA 1041+34 TO STA 1034+63 LT 1
 STA 1043+47 TO STA 1040+25 LT 1
 STAGE 2
 STA 1034+63 TO STA 1029+31 RT 1
 STA 1040+25 TO STA 1040+69 RT 1
 STAGE 3
 STA 1029+31 TO STA 1037+63 RT 1
 STA 1040+69 TO STA 1048+25 RT 1
 TOTAL = 12

Z0030360 IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 3
 LOCATION EACH REMARKS
 STAGE 3
 STA 1036+68 LT TO 1037+25 LT 1
 STA 1038+93 LT TO 1038+87 LT 1
 TOTAL = 2

Z0049838 REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1
 LOCATION L SUM REMARKS
 STA 1036+50.00 LT 1 HOUSE (NON-FRIABLE ASBESTOS)
 TOTAL = 1

Z0065740 SLOTTED DRAIN 12" WITH VARIABLE SLOT
 LOCATION EQQT REMARKS
 STA. 1040+67.08 TO 1041+03.08 LT 36.00 FLOW LINE 631.17 TO 631.12
 STA. 1041+12.61 TO 1041+70.61 LT 58.00 FLOW LINE 630.83 TO 630.80
 TOTAL = 94.00

X0322923 SEGMENTAL CONCRETE BLOCK WALL
 LOCATION SQ FT REMARKS
 STA 1034+12.68 TO STA 1035+37.32 872.48
 TOTAL = 872.48

X0326131 RELOCATE EXISTING TEMPORARY BRIDGE TRAFFIC SIGNALS
 LOCATION EACH REMARKS
 PRE-STAGE 4 1 SEE STAGING PLANS (REMAINS IN PLACE FOR 4 & 5)
 STAGE 1 1 SEE STAGING PLANS FOR NEW LOCATIONS
 STAGE 2 1 SEE STAGING PLANS FOR NEW LOCATIONS
 STAGE 3 1 SEE STAGING PLANS FOR NEW LOCATIONS
 TOTAL = 4

X0712400 TEMPORARY PAVEMENT
 LOCATION SQ YD REMARKS
 PRE-STAGE 1
 STA 1029+08.39 TO 1036+87.27 LT 1639.94
 STA 1038+82.27 TO 1048+06.87 LT 2119.44
 STAGE 1
 STA 1035+37.78 TO 1036+87.27 LT 253.40
 STA 1038+82.27 TO 1039+87.22 LT 280.04
 STAGE 2
 STA 1038+82.27 TO 1039+87.22 RT 235.95
 TOTAL = 4528.8

X0919000 TEMPORARY PAVEMENT REMOVAL
 LOCATION SQ YD REMARKS
 STA 1031+18.72 TO STA 1036+87.27 1178.91
 STA 1038+82.27 TO STA 1048+06.80 1579.46
 TOTAL = 2758.4

X6063401 COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.12
 LOCATION EQQT REMARKS
 STA 1041+02.48 TO STA 1041+14.32 71.21
 TOTAL = 71.21

CLASS SI CONCRETE (STEPS)
 LOCATION CU YD REMARKS
 STA 1045+40 LT 0.10
 STA 1045+98.40 LT 0.25
 TOTAL = 0.35

FILE NAME =	USER NAME = jordanhd	DESIGNED -	REVISED -
ea\pwork\NPWIDOT\JORDANHD\des34552\151205evr.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0/200' / IN.		CHECKED -	REVISED -
PLOT DATE = Mon Apr 27 15:25:51 2009		DATE -	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

----- SCHEDULE OF QUANTITIES -----			
SCALE: -----	SHEET NO. -- OF -- SHEETS	STA. ----- TO STA. -----	

F.A.P. RTE. 309	SECTION (17)B	COUNTY WHITESIDE	TOTAL SHEETS 376	SHEET NO. 29
CONTRACT NO. 64B74			ILLINOIS FED. AID PROJECT	