

# PAVEMENT SCHEDULE

STATIONING	REMARKS	LENGTH & WIDTHS				CONCRETE AREA		21001000	31100910	31100935	31100965	31100975	42000401
		PAVEMENT		ADDITIONAL SUB-B WIDTH (1 SIDE) FEET	SQ. FT.	SQ. YD.	GEO FAB FOR GROUND STAB SQ YD	SUB-BASE GRAN. MTRL. TYPE A, 12" SQ YD	SUB-BASE GRAN. MTRL. TYPE A, 18" SQ YD	SUB-BASE GRAN. MTRL. TYPE A, 24" SQ YD	SUB-BASE GRAN. MTRL. TYPE A, 30" SQ YD	PCC PAVEMENT 9" (JOINTED) SQ YD	
		LENGTH FEET	WIDTH FEET										
US 30 -- MAINLINE													
1031+30.05 - 1031+78.35		48.3	24.0 - 28.0	3.5	1255.80	139.53	177.10	177.10				139.53	
1031+78.35 - 1032+91.63		113.3	28.0 - 32.0	3.5	3398.40	377.60	465.71	465.71				377.60	
1032+91.63 - 1034+50.00		158.4	32.0	3.5	5067.84	563.09	686.27	686.27				563.09	
1034+50.00 - 1036+26.59		176.6	32.0	3.5	5650.88	627.88	765.22		765.22			627.88	
1036+26.59 - 1036+70.64		44.1	32.0 - 26.0	3.5	1277.45	141.94	176.20		176.20			141.94	
1036+70.64 - 1036+87.26		16.6	26.0	3.5	432.12	48.01	60.94		60.94			48.01	
1036+87.26 - 1038+82.27	BRIDGE												
1038+82.27 - 1040+50.00		167.7	26.0	3.5	4360.98	484.55	615.01	615.01				484.55	
1040+50.00 - 1042+50.00		200.0	26.0	3.5	5200.00	577.78	733.33		733.33			577.78	
1042+50.00 - 1044+60.07		210.1	26.0	3.5	5461.82	606.87	770.26			770.26		606.87	
1044+60.07 - 1045+37.03		77.0	26.0	3.5	2000.96	222.33	282.19			282.19		222.33	
1045+37.03 - 1045+50.00		13.0	26.0 - 24.0	3.5	324.25	36.03	46.12			46.12		36.03	
1045+50.00 - 1046+62.00		112.0	26.0 - 24.0	3.5	2800.00	311.11	398.22	398.22				311.11	
MILNES DR.													
1044+60.07		72.0	34.5	3.5	3640.32	404.48	482.65	482.65				404.48	
GRAND TOTALS								5659.21	2824.96	733.33	1002.36	1098.56	4541.20

# PAVEMENT PATCHING SCHEDULE

NEW STATION	REMARKS	LANE WIDTH		LENGTH OF		AREA OF		44200956		44200964		44213200	
		PATCH (FOOT)		PATCH (FOOT)		PATCH (SQ YD)		CLASS B PATCH		CLASS B PATCH		SAW CUTS	
		LT LANE	RT LANE	LT LANE	RT LANE	LT LANE	RT LANE	TYPE 2, 9" (SQ YD)		TYPE 4, 9" (SQ YD)		LT LANE	RT LANE
		WB	EB	WB	EB	WB	EB	WB	EB	WB	EB	FOOT	FOOT
1033 + 86		12	12	9.3	9.3	12.44	12.44	12.44	12.44			54.67	54.67
1036 + 36		12	12	9.3	9.3	12.44	12.44	12.44	12.44			54.67	54.67
1040 + 01		13	13	9.3	9.3	13.48	13.48	13.48	13.48			57.67	57.67
1042 + 45	FOR TRIPLE BOX CULVERT REMOVAL	27	28	70.0	70.0	210.00	217.78			210.00	217.78	221.00	224.00
1043 + 67	AT ANGLE	13	13	9.6	9.6	13.90	13.90	13.90	13.90			64.25	64.25
1045 + 40		13	12	9.9	9.9	14.32	13.22	14.32	13.22			58.83	55.83
1046 + 50		13	12	9.3	9.3	13.48	12.44	13.48	12.44			57.67	54.67
TOTAL								80.08	77.94	210.00	217.78	568.75	565.75
GRAND TOTAL								158.02		427.78		1134.50	