

# Summary of Quantities

Item #	Description	Unit	Quantity	80% FED		20% STATE	
				Y007 STA 886+50.9	Y007 STA 897+69.7	Y007 STA 710+76	
20200100	EARTH EXCAVATION	CU YD	1250	323	442	485	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	33	33	34	
20400800	FURNISHED EXCAVATION	CU YD	1093	278	273	542	
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	150.0	50	50	50	
25000210	SEEDING CLASS 2A	ACRE	0.5	0.16	0.17	0.17	
25000310	SEEDING CLASS 4	ACRE	0.25	0.09	0.09	0.07	
25000750	MOWING	ACRE	0.75	0.25	0.26	0.24	
25100115	MULCH METHOD 2	ACRE	0.75	0.25	0.26	0.24	
25100900	TURF REINFORCEMENT MAT	SQ YD	578	183	278	117	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	96	114	90	
28000300	TEMPORARY DITCH CHECKS	EACH	44	10	21	13	
28000400	PERIMETER EROSION BARRIER	FOOT	322	37	221	64	
28000500	INLET AND PIPE PROTECTION	EACH	4	1	1	2	
28100107	STONE RIPRAP, CLASS A4	SQ YD	27	27			
28200200	FILTER FABRIC	SQ YD	27	27			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	65	37		28	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	6.3	3.6		2.7	
44201433	CLASS C PATCHES, TYPE IV, 16 INCH	SQ YD	343	79	90	174	
44213200	SAW CUTS	FOOT	1177	308	403	466	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	118	41	51	26	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1			1	

\* Specialty Item  
 ) Non Participating  
**100% STATE**

FILE NAME =	USER NAME = fordjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL 40</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\pwork\fordjd\dms33783\0264D2-shit-500.dgn	DRAWN -	REVISED -	646			4T-2	Carroll	63	3	
PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 64D12							
PLOT DATE = Mon Mar 16 12:43:02 2009	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT