

# SCHEDULE OF QUANTITIES

PAY ITEM #	DESCRIPTION	UNIT	COMMENTS	PAY ITEM #	DESCRIPTION	UNIT	COMMENTS
20200100	EARTH EXCAVATION	CU YD		25100115	MULCH METHOD 2	ACRE	
	LOCATION				LOCATION		
	684+00 - 684+50	2.62			685+60 - 687+50 LT	0.12	
	684+50 - 685+00	7.48			685+60 - 687+50 RT	0.08	
	685+00 - 685+50	18.64			687+00 - 699+00 LT	0.13	
	685+50 - 686+00	37.0			696+50 - 699+00 RT	0.11	
	686+00 - 686+50	38.12			709+50 - 711+50 LT	0.13	
	686+50 - 687+00	128.38			710+00 - 712+00 RT	0.06	
	687+00 - 687+50	56.16			TOTAL =	0.64	
	687+50 - 688+00	21.99					
	688+00 - 688+50	8.78					
	688+50 - 689+00	3.94					
				25100900	TURF REINFORCEMENT MAT	SQ YD	
	695+50 - 696+00	6.56			LOCATION		
	696+00 - 696+50	20.86			686+00 - 686+35 LT	25.3	
	696+50 - 697+00	41.73			686+00 - 686+45 RT	30.6	
	697+00 - 697+50	78.94			686+55 - 687+50 LT	66.6	
	697+50 - 698+00	125.5			686+60 - 687+50 RT	60.5	
	698+00 - 698+50	90.56			697+00 - 697+45 LT	30.3	
	698+50 - 699+00	43.87			696+50 - 697+70 RT	83.5	
	699+00 - 699+50	20.04			697+70 - 698+00 LT	89.5	
	699+50 - 700+00	11.69			697+90 - 699+00 RT	74.9	
	700+00 - 700+50	3.19			710+00 - 710+10 LT	6.7	
					710+00 - 711+00 RT	67.7	
	708+00 - 708+50	3.4			710+50 - 710+74 LT	18.4	
	708+50 - 709+00	24.9			711+20 - 711+75 RT	36.8	
	709+00 - 709+50	45.7			TOTAL =	578	
	709+50 - 710+00	78.9					
	710+00 - 710+50	118.1		28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	
	710+50 - 711+00	88.9			LOCATION		
	711+00 - 711+50	49.2			685+60 - 687+50 LT	47.20	
	711+50 - 712+00	36.4			685+60 - 687+50 RT	33.20	
	712+00 - 712+50	20.6			697+00 - 699+00 LT	52.00	
	712+50 - 713+00	14.3			696+50 - 699+00 RT	45.20	
	713+00 - 713+50	4.6			709+50 - 711+50 LT	53.20	
	TOTAL =	1251			710+00 - 712+00 RT	24.80	
					TOTAL =	255.6	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD		28000300	TEMPORARY DITCH CHECKS	EACH	
	WHERE NECESSARY	100	If necessary		LOCATION		
	TOTAL =	100			686+00 - 686+35 LT	2	25' Centers
					686+00 - 686+45 RT	2	25' Centers
20400800	FURNISHED EXCAVATION	CU YD			686+55 - 687+00 LT	2	25' Centers
	LOCATION				687+00 - 687+50 LT	1	50' Centers
	685+50 - 687+50	278			686+60 - 687+00 RT	2	25' Centers
	696+50 - 699+00	273			687+00 - 687+50 RT	1	50' Centers
	709+50 - 712+00	542			697+00 - 697+45 LT	3	20' Centers
	TOTAL =	1093			696+50 - 697+00 RT	4	17' Centers
					697+00 - 697+70 RT	3	20' Centers
21301052	EXPLORATION TRENCH 52" *	FOOT			697+70 - 698+00 LT	2	33' Centers
	Where Necessary	300			698+00 - 698+50 LT	2	25' Centers
	TOTAL =	300			698+00 - 698+50 RT	3	25' Centers
					698+50 - 699+00 LT	1	50' Centers
					698+50 - 699+00 RT	3	15' Centers
					710+00 LT	1	
					710+45 - 710+75 LT	3	13' Centers
					710+00 - 710+50 RT	4	17' Centers
					710+50 - 711+00 RT	2	25' Centers
					711+20 - 711+25 RT	3	25' Centers
					TOTAL =	44	
25000210	SEEDING CLASS 2A	ACRE		28000400	PERIMETER EROSION BARRIER	FOOT	
	LOCATION				LOCATION		
	685+60 - 687+50 LT	0.06			686+00 - 686+35 40' LT - 53' LT	37.3	
	685+60 - 687+50 RT	0.06			697+00 - 697+50 40' LT - 58' LT	53.1	
	697+00 - 699+00 LT	0.07			698+00 - 699+00 48' RT - 30' RT	101.6	
	696+50 - 699+00 RT	0.09			697+00 - 697+65 43' RT - 53' RT	65.8	
	709+50 - 711+50 LT	0.08			710+50 - 711+00 95.0' LT - 55.0' LT Along New ROW Line Prior to Stage 1	64	
	710+00 - 712+00 RT	0.06			TOTAL =	321.8	
	TOTAL =	0.43					
25000310	SEEDING CLASS 4	ACRE		28000500	INLET AND PIPE PROTECTION	EACH	
	LOCATION				LOCATION		
	685+60 - 687+50 LT	0.05			686+53.4 28.4' RT	1	
	685+60 - 687+50 RT	0.02			697+80.6 40.6' RT	1	
	697+00 - 699+00 LT	0.06			711+09.8 35.9' RT	1	
	696+50 - 699+00 RT	0.02			711+47.1 32.3' LT	1	
	709+50 - 711+50 LT	0.05			TOTAL =	4	
	710+00 - 712+00 RT	0.00					
	TOTAL =	0.21					