

# SCHEDULE OF QUANTITIES

| PAY ITEM# | DESCRIPTION   | UNIT   | COMMENTS       |
|-----------|---|--------|----------------|
| 78001110  | PAINT PAVEMENT MARKING LINE, 4"                                       | FOOT   |                |
|           | <u>LOCATION</u>   |        |                |
|           | 685+00 - 687+60 LT - EDGE LINE (WHITE)                                | 520    | 2 APPLICATIONS |
|           | 685+00 - 687+60 RT - EDGE LINE (WHITE)                                | 520    | 2 APPLICATIONS |
|           | 685+00 - 687+60 DOUBLE LINE (YELLOW)                                  | 1040   | 2 APPLICATIONS |
|           | 696+30 - 699+20 LT - EDGE LINE (WHITE)                                | 580    | 2 APPLICATIONS |
|           | 696+30 - 699+20 RT - EDGE LINE (WHITE)                                | 580    | 2 APPLICATIONS |
|           | 696+30 - 699+20 DOUBLE LINE (YELLOW)                                  | 1160   | 2 APPLICATIONS |
|           | 709+30 - 712+20 LT - EDGE LINE (WHITE)                                | 580    | 2 APPLICATIONS |
|           | 709+30 - 712+20 RT - EDGE LINE (WHITE)                                | 580    | 2 APPLICATIONS |
|           | 709+30 - 712+20 SKIP DASH (YELLOW)                                    | 146    | 2 APPLICATIONS |
|           | 709+30 - 712+20 LINE (YELLOW)   | 580    | 2 APPLICATIONS |
|           | TOTAL =   | 6286   |                |
| 78300100  | PAVEMENT MARKING REMOVAL  | SQ FT  |                |
|           | <u>LOCATION</u>   |        |                |
|           | 684+29.43 - 689+39.7 LT   | 170.1  |                |
|           | 682+56.8 - 690+20.3 RT  | 254.6  |                |
|           | 682+56.8 - 690+20.3 CENTER  | 509.1  |                |
|           | 695+17.1 - 700+73.3 LT  | 185.4  |                |
|           | 693+81.3 - 701+39.7 RT  | 259.5  |                |
|           | 693+81.3 - 701+39.7 CENTER  | 518.9  |                |
|           | 708+07.3 - 713+97.6 LT  | 196.8  |                |
|           | 706+31.7 - 714+69.0 RT  | 279.1  |                |
|           | 706+31.7 - 714+69.0 CENTER  |        |                |
|           | TOTAL =   | 2373.5 |                |
| X0323660  | DROP BOX NO. 1  | EACH   |                |
|           | <u>LOCATION</u>   |        |                |
|           | 711+08.5 RT   | 1      |                |
|           | TOTAL =   | 1      |                |
| X0712400  | TEMPORARY PAVEMENT  | SQ YD  |                |
|           | <u>LOCATION</u>   |        |                |
|           | 684+29.4 - 685+18.0 LT (Stage 2)                                      | 38.8   |                |
|           | 685+50.0 - 688+93.4 LT (Stage 2)                                      | 367.3  |                |
|           | 696+30.9 - 699+00.4 RT (Stage 1)                                      | 94.2   |                |
|           | 695+32.7 - 700+13.9 LT (Stage 2)                                      | 475.3  |                |
|           | 709+30.6 - 712+20.9 RT (Stage 1)                                      | 97.6   |                |
|           | 708+12.1 - 713+44.7 LT (Stage 2)                                      | 562.2  |                |
|           | TOTAL =   | 1835.4 |                |
| X0919000  | TEMPORARY PAVEMENT REMOVAL  | SQ YD  |                |
|           | <u>LOCATION</u>   |        |                |
|           | 685+50 - 688+57.8   | 257.9  |                |
|           | 685+77.6 - 699+80.8   | 327.7  |                |
|           | 708+45.4 - 713+10.9   | 392.2  |                |
|           | TOTAL =   | 977.8  |                |
| Z0030250  | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL III       | EACH   |                |
|           | <u>LOCATION</u>   |        |                |
|           | 687+70.7 5.1' LT (Stage 1)  | 1      |                |
|           | 699+11.2 5.9' LT (Stage 1)  | 1      |                |
|           | TOTAL =   | 2      |                |
| Z0030350  | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL III        | EACH   |                |
|           | <u>LOCATION</u>   |        |                |
|           | 686+07.5 to 686+24 12.3' LT (Stage 2) narrow device                   | 1      |                |
|           | 686+24 to storage narrow device                                       | 1      |                |
|           | 687+70.7 to 689+11.6 5.3' RT (Stage 2)                                | 1      |                |
|           | 689+11.6 to 696+22.0 5.7' LT (Stage 1)                                | 1      |                |
|           | 696+22 to 695+15.9 5.3' RT (Stage 2)                                  | 1      |                |
|           | 699+11.2 to 700+29.3 5.4' RT (Stage 2)                                | 1      |                |
|           | 700+29.3 to storage   | 1      |                |
|           | 695+15.9 to 709+18.3 5.2' LT (Stage 1)                                | 1      |                |
|           | from storage to 711+07.0 3.2' RT (Stage 1) narrow device              | 1      |                |
|           | 709+18.3 to 708+93.8 2.8' LT (Stage 2)                                | 1      |                |
|           | from storage to 713+57.2 5.5' RT (Stage 2)                            | 1      |                |
|           | TOTAL =   | 11     |                |
| XZ030260  | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3 | EACH   |                |
|           | <u>LOCATION</u>   |        |                |
|           | 686+07.5 1.19' RT (Stage 1)   | 1      |                |
|           | TOTAL =   | 1      |                |