

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED 10% STATE
				NONE SFTY - 2A RURAL
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	19	19
20200100	EARTH EXCAVATION	CU YD	2,650	2,650
* 25000210	SEEDING, CLASS 2A	ACRE	0.82	0.82
:) 25000750	MOWING	ACRE	0.82	0.82
25100115	MULCH, METHOD 2	ACRE	0.82	0.82
25100630	EROSION CONTROL BLANKET	SQ YD	584	584
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	492	492
28000300	TEMPORARY DITCH CHECKS	EACH	10	10
28000400	PERIMETER EROSION BARRIER	FOOT	960	960
28000500	INLET AND PIPE PROTECTION	EACH	8	8
28100107	STONE RIPRAP, CLASS A4	SQ YD	22	22
28200200	FILTER FABRIC	SQ YD	22	22
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	1947	1947
35101400	AGGREGATE BASE COURSE, TYPE B	TON	277	277
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6.1	6.1
40600300	AGGREGATE (PRIME COAT)	TON	13	13
40600735	POLYMERIZED LEVELING BINDER (HAND METHOD), N70	TON	4	4
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	468	468
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	221	221
40600990	TEMPORARY RAMP	SQ YD	87	87
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	771	771
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	278	278
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	562	562

* SPECIALTY ITEMS

:) NON PARTICIPATING 100% STATE

FILE NAME = c:\pwork\pwork\DWG\DOSSDD\dms41852\08706	USER NAME = dossdd 6cwr.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 553	SECTION 120M	COUNTY OGLE	TOTAL SHEETS 71	SHEET NO. 3
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 64E55		
PLOT DATE = Tue Jan 13 15:27:51 2009	DATE -	REVISED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT								