

PAVED SHOULDER REMOVAL

SQ.YD	LOCATION
	IL 251
81.8	Sta 781 + 06 - 782 + 30 LT
70.0	Sta 781 + 06 - 782 + 30 RT
151.8	TOTAL

CLASS C PATCHES, TYPE IV, 9 INCH

SQ.YD	LOCATION
	IL 72
128.4	Sta 1785 + 16 - 1785 + 56 (L = 40')
120.1	Sta 1787 + 32 - 1787 + 72 (L = 40')
248.5	TOTAL

STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION
	IL 72
365	Sta 1782 + 84 - 1786 + 08 LT
310	Sta 1783 + 31 - 1786 + 08 RT
160	Sta 1786 + 36 - 1787 + 64 LT
215	Sta 1786 + 36 - 1788 + 18 RT
	IL 251
195	Sta 784 + 74 - 786 + 63 LT
160	Sta 785 + 00 - 786 + 54 RT
95	Sta 788 + 08 - 788 + 97 LT
145	Sta 787 + 87 - 789 + 28 RT
1,845	TOTAL

AGGREGATE WEDGE SHOULDERS, TYPE B

TON	LOCATION
	IL 72
3.0	Sta 1782 + 34 - 1782 + 84 RT
8.4	Sta 1788 + 81 - 1789 + 31 RT
	IL 251
4.0	Sta 789 + 93 - 790 + 43 LT
6.8	Sta 789 + 93 - 790 + 43 RT
25.0	As Needed & Directed by the Resident
47.2	TOTAL

REMOVAL OF EXISTING STRUCTURE NO. 1

EACH	LOCATION
	IL 72
1	Sta 1785 + 31 (4' X 1.5' RC Culvert)
1	TOTAL

REMOVAL OF EXISTING STRUCTURE NO. 2

EACH	LOCATION
	IL 72
1	Sta 1787 + 49 (42" AD EQ RCCP, & 3' 2' RC Culvert)
1	TOTAL

PIPE CULVERTS, CLASS D, TYPE 1 15"

FOOT	LOCATION
	IL 72
79	Sta 1788 + 38 LT
	IL 251
50	Sta 789 + 50 RT
129	TOTAL

PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 15"

FOOT	LOCATION
	IL 72
64	Sta 1788 + 14 RT
64	TOTAL

PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 18"

FOOT	LOCATION
	IL 72
56	Sta 1783 + 21 RT
65	Sta 1784 + 87 RT
121	TOTAL

PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"

FOOT	LOCATION
	IL 72
152	Sta 1785 + 31 LT (38' X 4 Pipes)
148	Sta 1785 + 31 RT (37' X 4 Pipes)
104	Sta 1787 + 52 LT (26' x 4 Pipes)
104	Sta 1787 + 52 RT (26' x 4 Pipes)
508	TOTAL