

**MAINLINE SCHEDULE**

LOCATION IL 17	LENGTH	WIDTH	HMA SURF	HMA SURF	HMA SURF	LEVEL.	MIX	LEVEL	BITUMINOUS	AGG	HMA SURF	TEMP	AGG
			REM	REM	COURSE	BINDER	FOR CRACKS	BINDER	MATERIALS	(PRIME	REMOVAL	RAMP	SHLDS
	FT	FT	WIDTH	3/4"	1 1/2"	3/4"	JOINTS AND	HAND	(PRIME	COAT)	BUTT JT.	SQ YD	TONS
			FT	SQ YD	TONS	TONS	FLANGEWAYS	METHOD	COAT)	TONS	SQ YD	SQ YD	TONS
<b>LASALLE COUNTY</b>													
<b>BEGIN PROJECT NORTH OF US 52 (300')</b>													
STA 669+25 TO 669+85	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
STA 669+85 TO 679+99	1014.00	34.00	30.0	3380.0	321.8	142.0	1.01	1.7	273.1	6.8			115.5
STA 679+99 TO STA 680+59	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
<b>BRIDGE OMISSION STA 680+59 TO STA 680+85</b>													
STA 680+85 TO STA 681+45	60.00	34.00	30.0	200.0	19.0	1.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
STA 681+45 TO STA 682+53	108.00	34.00	30.0	360.0	34.3	15.1	0.11	0.2	31.5	0.8			12.3
STA 682+53 TO 683+13	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
<b>BRIDGE OMISSION STA 683+13 TO STA 683+43</b>													
STA 683+43 TO STA 684+03	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
STA 684+03 TO STA 753+62	6959.00	34.00	30.0	23,196.7	2208.3	974.3	6.96	11.6	1858.5	46.5			792.6
STA 753+62 TO STA 754+22	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
<b>BRIDGE OMISSION STA 754+22 TO STA 754+48</b>													
STA 754+48 TO STA 755+08	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
STA 755+08 TO STA 867+80	11,272.00	34.00	30.0	37,573.3	3577.0	1578.1	11.27	18.8	3008.6	75.2			1283.8
STA 867+80 TO STA 868+40	60.00	34.00	30.0	200.0	19.0	8.4	0.06	0.1	18.7	0.5	200.0	12.2	6.8
<b>END OF PROJECT KENDALL COUNTY LINE</b>													
<b>TOTAL</b>	<b>19,915.0</b>			<b>66,110.0</b>	<b>6293.4</b>	<b>2769.7</b>		<b>19.8</b>	<b>5,321.4</b>	<b>133.1</b>	<b>1600.0</b>	<b>97.8</b>	<b>2258.8</b>

**ENTRANCE SCHEDULE**

DESCRIPTION	NUMBER OF LOCATIONS	AREA	TOTAL AREA	INC.	BIT.	AGG.	FURNISHED EXCAVATION	HMA SURF. REM.	TEMP
				HMA SURF.	MAT'L (PR. CT.)	(PR. CT.)		BUTT JT	RAMPS
		SQ YD		TON	GAL	TON	CU YD	SQ YD	SQ YD
<b>LASALLE COUNTY</b>									
PRIVATE ENTRANCE	17.00	33.33	566.67	47.60	45.30	1.13		150.00	
SIDERoadS	5.00	142.90	714.50	60.00	11.40	0.29	12.50	167.00	85.00
MAILBOX TURNOUTS	11.00	20.40	224.40	18.80	1.60	0.04			
<b>TOTAL</b>				<b>126.4</b>	<b>58.3</b>	<b>1.46</b>	<b>12.5</b>	<b>317</b>	<b>85</b>

**CLASS D PATCHING, 12 INCHES**

STA.	SIDE	LENGTH	TYPE II	TYPE III
		FT	SQ YD	SQ YD
672+85	NB	6	8.7	
672+85	SB	6	8.7	
693+55	NB	6	8.7	
715+15	SB	6	8.7	
746+25	NB	6	8.7	
748+40	NB	6	8.7	
760+85	NB	15		21.7
760+85	SB	6	8.7	
785+85	NB	6	8.7	
785+85	SB	6	8.7	
820+25	NB	7	10.1	
824+00	NB	6	8.7	
824+00	SB	6	8.7	
827+25	SB	6	8.7	
827+30	NB	6	8.7	
831+05	SB	6	8.7	
<b>TOTALS</b>			<b>131</b>	<b>22</b>

**PAVEMENT MARKING**

LOCATION	PAINT PVMT MK				TEMPORARY PVMT MK			SHORT TERM PAVT MK	WORK ZONE PAVT MK REM	
	LENGTH	4"		6"	4"		6"			
		LIN FT	WHITE	YELLOW	YELLOW	WHITE	YELLOW			YELLOW
<b>LASALLE COUNTY</b>										
<b>BEGIN PROJECT NORTH OF US 52 (300')</b>										
STA 669+25 TO 669+85	60.0		120.0		15.0	120.0		15.0	18.0	2.0
STA 669+85 TO 679+99	1014.0		2028.0	NPL	253.5	2028.0	NPL	253.5	304.2	33.8
STA 679+99 TO STA 680+59	60.0		120.0		15.0	120.0		15.0	18.0	2.0
<b>BRIDGE - STA 680+59 TO STA 680+85</b>										
STA 680+59 TO STA 681+45	86.0		172.0		21.5	172.0		21.5	25.8	2.9
STA 681+45 TO STA 682+53	108.0		216.0	NPL	27.0	216.0	NPL	27.0	32.4	3.6
STA 682+53 TO 683+13	60.0		120.0		15.0	120.0		15.0	18.0	2.0
<b>BRIDGE - STA 683+13 TO STA 683+43</b>										
STA 683+43 TO STA 684+03	90.0		180.0		22.5	180.0		22.5	27.0	3.0
STA 684+03 TO STA 753+62	6959.0		13,918.0	NPL	1739.8	13,918.0	NPL	1739.8	2087.7	231.7
STA 753+62 TO STA 754+22	60.0		120.0		15.0	120.0		15.0	18.0	2.0
<b>BRIDGE - STA 754+22 TO STA 754+48</b>										
STA 754+48 TO STA 755+08	86.0		172.0		21.5	172.0		21.5	25.8	2.9
STA 755+08 TO STA 866+50	11,142.0		22,284.0	NPL	2785.5	22,284.0	NPL	2785.5	3342.6	371.0
STA 866+50 TO STA 868+40	190.0		380.0		47.5	380.0		47.5	57.0	6.3
<b>TOTAL</b>	<b>19,915</b>		<b>39,830</b>		<b>5284</b>	<b>39,830</b>		<b>5284</b>	<b>5975</b>	<b>663</b>

**RAISED REFLECTIVE MARKERS**

LOCATION	2 WAY	REMOVAL
	AMBER EACH	EACH
LASALLE CO		
STA 669+25 TO STA 868+40	246	246
<b>TOTAL</b>	<b>246</b>	<b>246</b>

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**5-8-09 MJ SCHEDULES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(3)RS-2	LASALLE	8	6
CONTRACT NO. 66434				
ILLINOIS FED. AID PROJECT				

FILE NAME = c:\pwork\PWIDOT\SCHWANKER\0131387\11shs.dgn  
 USER NAME = schwankerg  
 DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -  
 PLOT SCALE = 40.0000' / IN.  
 PLOT DATE = May 08, 2009 - 10:09:54 AM

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -