

STATION TO		STATION		EARTHWORK SCHEDULE			
		EARTH EX (WIDENING)	EARTH EX ADJ FOR SHRINKAGE	EMBANKMENT	EARTHWORK BAL WASTE (+) OR SHORTAGE (-)		
		CU YD	CU YD	CU YD	CU YD		
1+90	TO	3+30	5	4	1	3	
3+30	TO	5+40	16	12	2	10	
5+40	TO	13+12	53	40	4	36	
13+12	TO	19+68	46	35	6	29	
19+68	TO	26+24	44	33	11	22	
26+24	TO	32+80	45	34	10	24	
32+80	TO	39+36	48	36	8	28	
39+36	TO	45+93	50	38	8	30	
45+93	TO	55+77	76	57	15	42	
55+77	TO	59+05	24	18	7	11	
59+05	TO	65+61	47	35	12	23	
65+61	TO	72+17	46	35	11	24	
72+17	TO	78+73	46	35	11	24	
78+73	TO	85+30	42	32	8	24	
85+30	TO	91+86	47	35	10	25	
91+86	TO	98+42	42	32	17	15	
98+42	TO	104+98	44	33	15	18	
104+98	TO	111+54	42	32	15	17	
111+54	TO	114+82	20	15	9	6	
114+82	TO	127+95	41	31	9	22	
127+95	TO	131+23	23	17	5	12	
131+23	TO	137+79	42	32	15	17	
137+79	TO	144+35	32	24	14	10	
144+35	TO	150+91	40	30	19	11	
150+91	TO	157+47	40	30	16	14	
157+47	TO	164+04	42	32	10	22	
164+04	TO	170+60	45	34	11	23	
170+60	TO	177+16	45	34	9	25	
177+16	TO	183+72	49	37	10	27	
183+72	TO	190+28	47	35	12	23	
190+28	TO	196+84	42	32	10	22	
196+84	TO	203+41	54	41	7	34	
203+41	TO	209+97	54	41	6	35	
209+97	TO	216+53	49	37	8	29	
216+53	TO	223+09	52	39	7	32	
223+09	TO	229+65	54	41	6	35	
229+65	TO	236+21	47	35	6	29	
236+21	TO	239+11	21	16	4	12	
239+11	TO	241+81					
241+81	TO	242+78	6	5	2	3	
242+78	TO	249+34	45	34	9	25	
249+34	TO	255+90	43	32	9	23	
255+90	TO	262+46	49	37	10	27	
262+46	TO	269+02	49	37	9	28	
269+02	TO	275+58	53	40	7	33	
275+58	TO	282+15	47	35	8	27	
282+15	TO	288+71	47	35	9	26	
288+71	TO	295+27	44	33	11	22	
295+27	TO	301+83	42	32	12	20	
301+83	TO	308+39	44	33	11	22	
308+39	TO	314+95	42	32	9	23	
314+95	TO	321+52	37	28	8	20	
321+52	TO	328+08	44	33	7	26	
328+08	TO	334+64	46	35	8	27	
334+64	TO	341+20	41	31	11	20	
341+20	TO	347+76	40	30	11	19	
347+76	TO	354+32	42	32	10	22	
354+32	TO	360+89	46	35	9	26	
360+89	TO	367+45	47	35	8	27	
367+45	TO	374+01	55	41	7	34	
374+01	TO	380+57	55	41	8	33	
380+57	TO	387+13	49	37	7	30	
387+13	TO	393+69	49	37	8	29	
393+69	TO	400+26	44	33	10	23	
400+26	TO	406+82	42	32	11	21	
406+82	TO	410+49	27	20	5	15	
410+49	TO	444+59					
444+59	TO	445+40	7	5	0	5	
445+40	TO	451+13	53	40	2	38	
451+13	TO	451+46					
451+46	TO	452+75	10	8	1	7	
452+75	TO	459+31	55	41	6	35	
459+31	TO	465+87	55	41	5	36	
465+87	TO	472+43	49	37	7	30	
472+43	TO	479+00	47	35	10	25	
479+00	TO	485+56	49	37	8	29	
485+56	TO	492+12	55	41	5	36	
492+12	TO	498+68	56	42	4	38	
498+68	TO	501+55	26	20	1	19	
501+55	TO	501+80					
501+80	TO	505+24	28	21	3	18	
505+24	TO	511+80	49	37	9	28	
511+80	TO	518+37	47	35	11	24	
518+37	TO	523+29	38	29	6	23	
523+29	TO	524+18	7	5	2	3	
524+18	TO	525+70	8	6	2	4	
TOTALS			3416	2574	680	1894	