

SUMMARY OF QUANTITIES				
CONSTRUCTION CODE SFTY-2A				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL 100% STATE
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	2,232	2,232
44200541	CLASS A PATCHES, TYPE II, 9 INCH	SQ YD	100	100
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SQ YD	1112	1112
50102400	CONCRETE REMOVAL	CU YD	56	56
50300225	CONCRETE STRUCTURES	CU YD	12	12
50300255	CONCRETE SUPERSTRUCTURE	CU YD	44	44
50300260	BRIDGE DECK GROOVING	SQ YD	1,134	1,134
50300300	PROTECTIVE COAT	SQ YD	1,200	1,200
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	10,344	10,344
50800515	BAR SPLICERS	EACH	100	100
52000110	PREFORMED JOINT STRIP SEAL	FOOT	170	170
59000200	EPOXY CRACK INJECTION	FOOT	29	29
67100100	MOBILIZATION	L SUM	1	1
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	2	2
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	750	750
X 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,820	2,820
X 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	520	520
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,190	1,190
X0321468	PLUG EXISTING DECK DRAINS	EACH	4	4
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	73	73
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	2,177	2,177
X0323491	SLOPE WALL CRACK SEALING	FOOT	67	67
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	96	96
Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	SQ YD	2,177	2,177
50300530	FLOOR DRAIN EXTENSION	EACH	5	5
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	40	40
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0032470	JOINT SEALER	FOOT	119	119
Z0065700	SLOPE WALL REPAIR	SQ YD	15	15

X SPECIALTY
ITEM

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RON WOODSHANK	REVISED -
ct:\pw\work\PW1001\WOODSHANKRL\dms91655	03-66898-details.dgn	DRAWN - RON WOODSHANK	REVISED -
PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISOR -	REVISED -
PLOT DATE = Mar 25, 2009 - 08:57:21 AM	DATE -	REVISOR -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	(50-7B)I-2	LASALLE	29	3
FED. ROAD DIST. NO. (ILLINOIS)			CONTRACT NO. 66890	