

## SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: SFTY-2A

CODE NO.	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITY
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	30
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	374
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4
50102400	CONCRETE REMOVAL	CU YD	23
5057300	<del>CONCRETE SUPERSTRUCTURE</del> <b>PROTECTIVE SHIELD</b>	<del>CU YD</del> <b>SQ YD</b>	<del>25</del> <b>250</b>
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25
50300260	BRIDGE DECK GROOVING	SQ YD	559
50300300	PROTECTIVE COAT	SQ YD	626
50606400	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1
50607900	CLEANING <sup>AND</sup> PAINTING <sup>METAL</sup> HANDRAIL	FOOT	466
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2210
52000110	PREFORMED JOINT STRIP SEAL	FOOT	134
67100100	MOBILIZATION	L SUM	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
X 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	700
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	568
X0323078	REMOVE AND RE-ERECT EXISTING BRIDGE RAIL	FOOT	<del>228</del>
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	13
X5067500	<del>BRIDGE CLEANING AND PAINTING WARRANTY</del>	L SUM	1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	568
50300530	FLOOR DRAIN EXTENSION	EACH	16
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SQ YD	30

X SPECIALTY  
ITEM