

CLASS A PATCHING SCHEDULE - NBL

LOCATION BY MILE MARKER	PASSING LANE				DRIVING LANE				REMARKS
	PATCHING TYPE II	PATCH REINF.	PAV'T FABRIC	SAW CUTS	PATCHING TYPE II	PATCH REINF.	PAV'T FABRIC	SAW CUTS	
	SO YD	SO YD	SO YD	FOOT	SO YD	SO YD	SO YD	FOOT	
263.70									PROJECT BEGIN: FORD COUNTY LINE
269.80	8	8	8	66	8	8	8	66	
270.00					8	8	8	66	
271.40					8	8	8	66	
272.20									BUCKLEY INTERCHANGE
277.50					8	8	8	66	
277.60					8	8	8	66	
278.90					8	8	8	66	
280.20									IL RTE 54 INTERCHANGE
282.90					8	8	8	66	
283.10									IL RTE 24 INTERCHANGE
284.30	8	8	8	66					
287.00	8	8	8	66					
290.05					8	8	8	66	
290.20	8	8	8	66	8	8	8	66	
290.25					8	8	8	66	
290.40					8	8	8	66	
290.41	8	8	8	66					
290.70					8	8	8	66	
291.50					8	8	8	66	
291.60					8	8	8	66	
291.80	8	8	8	66					
291.90					8	8	8	66	
292.20	8	8	8	66					
292.23					8	8	8	66	
292.40					8	8	8	66	
292.80									IL RTE 116 INTERCHANGE
293.10					8	8	8	66	
293.80	8	8	8	66	8	8	8	66	
294.00					8	8	8	66	
295.60					8	8	8	66	
295.70	8	8	8	66	8	8	8	66	
295.75					8	8	8	66	
296.60									CLIFTON INTERCHANGE
301.70									CHEBANSE INTERCHANGE
301.90									END PROJECT: KANKAKEE COUNTY LINE
TOTALS	72	72	72	594	184	184	184	1518	

CLASS A PATCHING SCHEDULE - SBL

LOCATION BY MILE MARKER	PASSING LANE				DRIVING LANE				REMARKS
	PATCHING TYPE II	PATCH REINF.	PAV'T FABRIC	SAW CUTS	PATCHING TYPE II	PATCH REINF.	PAV'T FABRIC	SAW CUTS	
	SO YD	SO YD	SO YD	FOOT	SO YD	SO YD	SO YD	FOOT	
301.90									PROJECT BEGIN: KANKAKEE COUNTY LINE
301.70									CHEBANSE INTERCHANGE
299.50					8	8	8	66	APPROACH PAVEMENT
298.30					8	8	8	66	
298.20	8	8	8	66					
297.95	8	8	8	66	8	8	8	66	
296.70									CLIFTON INTERCHANGE
296.60					8	8	8	66	RAMP
296.30					8	8	8	66	RAMP
296.29					8	8	8	66	
296.27	8	8	8	66	8	8	8	66	
296.20	8	8	8	66					
296.00					13	13	13	78	
295.95	8	8	8	66					
295.93	8	8	8	66					
295.30					8	8	8	66	
295.00					8	8	8	66	
294.40					8	8	8	66	
294.30					8	8	8	66	
293.50	8	8	8	66	8	8	8	66	
293.40	8	8	8	66					
293.00					8	8	8	66	
292.90									IL RTE 116 INTERCHANGE
292.70					8	8	8	66	
292.55					8	8	8	66	
292.53	8	8	8	66					
292.15	8	8	8	66					
292.12					8	8	8	66	
291.33					8	8	8	66	
291.10	8	8	8	66	8	8	8	66	
290.60					8	8	8	66	
290.58					8	8	8	66	
290.35	8	8	8	66					
290.30					8	8	8	66	
290.20					8	8	8	66	
285.70	8	8	8	66					
284.37	8	8	8	66	8	8	8	66	
283.10									IL RTE 24 INTERCHANGE
281.20					8	8	8	66	
281.10	8	8	8	66					
280.75					8	8	8	66	
280.60					8	8	8	66	
280.50	8	8	8	66					
280.40	8	8	8	66	8	8	8	66	
280.20									IL RTE 54 INTERCHANGE
279.90	8	8	8	66	8	8	8	66	
279.80					8	8	8	66	
276.40					8	8	8	66	
276.20					8	8	8	66	
275.55					8	8	8	66	
275.10					8	8	8	66	
275.00					8	8	8	66	
274.95					8	8	8	66	
274.93					8	8	8	66	
272.20									BUCKLEY INTERCHANGE
271.30	8	8	8	66	8	8	8	66	
267.90					8	8	8	66	
263.70									END PROJECT: FORD COUNTY LINE
TOTALS	152	152	152	1254	317	317	317	2586	

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RLW	REVISED - ---
cr\pw\work\PW\DOT\WOODSHANKRL\dms91716	D3-66966-details.dgn	DRAWN - RLW	REVISED - ---
	PLOT SCALE = 100.0000 / IN.	CHECKED - ---	REVISED - ---
	PLOT DATE = Mar 26, 2009 - 11:15:05 AM	DATE - ---	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: _____ SHEET NO. 1 OF 4 SHEETS

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	D3 PAVEMENT PATCHING 2010-4	IROUOIS	9	8
FED. ROAD DIST. NO. - [ILLINOIS]			CONTRACT NO.66966	