

SUMMARY OF QUANTITIES					RS	HSIP	
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000 80/20 FED. ST.	SFTY-ID 90/10 FED. ST.	1000 100% STATE	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	65	65			
40600300	AGGREGATE (PRIME COAT)	TON	376	376			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3623	3623			
40600990	TEMPORARY RAMP	SQ YD	707	707			
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	10645	10645			
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	125492	125492			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3001	3001			
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	2513	2513			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	46	46			
63200310	GUARDRAIL REMOVAL	FOOT	3156	3156			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4			
67100100	MOBILIZATION	L SUM	1	1			
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	18932	18932			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	149936	149936			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1578	1578			
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 4"	FOOT	55276		55276		
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-LINE 6"	FOOT	94660		94660		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	386	386			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	57	57			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	46	46			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1000	1000			
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	738	738			
X0320614	CENTER JOINT REPAIR SYSTEM	FOOT	4250	4250			
X0322729	MATERIAL TRANSFER DEVICE	TON	10645	10645			
X2503100	MOWING	UNIT	948			948	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5271	5271			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1			

* SPECIALTY ITEM

FILE NAME = Typical Section.dgn	USER NAME = lobabidiam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 26 SUMMARY OF QUANTITIES	F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -			2370	(29,32,33,34)RS-3	WOODFORD	56	44	
		CHECKED -	REVISED -			CONTRACT NO. 68401					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	