

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685		FULTON	19	3
STA. 198+00		TO STA. 202+25		
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT		
* D4 CULVERT EXT.2008				

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES		UNIT	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM		TOTAL QTY	SFTY 2A
20100500	TREE REMOVAL, ACRES	ACRE	0.9	0.9
20200100	EARTH EXCAVATION	CU YD	4548	4548
21101625	TOPSOIL, FURNISH AND PLACE, 6"	SQ YD	3753	3753
25000200	SEEDING, CLASS 2	ACRE	0.8	0.8
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72
25100630	EROSION CONTROL BLANKET	SQ YD	3753	3753
28000300	TEMPORARY DITCH CHECKS	EACH	15	15
28000400	PERIMETER EROSION BARRIER	FOOT	203	203
28100227	STONE RIPRAP, CLASS B4	TON	60	60
28200200	FILTER FABRIC	SQ YD	90	90
48101200	AGGREGATE SHOULDERS, TYPE B	TON	58	58
50800105	REINFORCEMENT BARS	POUND	50	50
52102965	ANCHOR BOLTS, 3/4"	EACH	16	16
54202965	PIPE CULVERTS, TYPE 4, RCCP 30"	FOOT	64	64
54202977	PIPE CULVERTS, TYPE 4, RCCP 42"	FOOT	68	68
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTION, 30"	EACH	1	1
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTION, 42"	EACH	1	1
54248510	CONCRETE COLLAR	CU YD	1.0	1.0
63200310	GUARDRAIL REMOVAL	FOOT	338	338
66500105	WOVEN WIRE FENCE, 4'	FOOT	571	571
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	425	425
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4	4
67100100	MOBILIZATION	L. SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1	1

REVISIONS	
NAME	DATE
M.M.A., K.K.K.	04/30/2009

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 09/19/2008

DRAWN BY: BALSER
DESIGNED BY: PETERSON
CHECKED BY: BRUNER