

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685		FULTON	19	4
STA. 198+00		TO STA. 202+25		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* D4 CULVERT EXT. 2008				

SCHEDULES OF QUANTITIES

MOBILIZATION	
LOCATION	L. SUM
JOBSITE	1
TOTAL=	1

EARTHWORK SCHEDULE					
LOCATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL, FURNISH AND PLACE, 6"
	CU YD	CU YD	CU YD	CU YD	SQ YD
STA. 198+25.00 TO STA. 202+00.00, RT.	4548	3411	2761	650 (+)	3753
TOTAL=	4548	3411	2761	650 (+)	3753

SHRINKAGE FACTORS: EARTH EXCAVATION 25%

NITROGEN FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
STA. 198+25 TO STA. 202+00	72
TOTAL=	72

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
LOCATION	L. SUM
JOBSITE	1
TOTAL=	1

PERIMETER EROSION BARRIER	
LOCATION	QTY. (FOOT)
199+46.00, 120' RT. TO STA. 199+85.00, 190' RT.	80
STA. 199+85.00, 190' RT. TO STA. 200+25.00, 180' RT.	41
STA. 200+25.00, 180' RT. TO STA. 200+75.00, 115' RT.	82
TOTAL=	203

TOPSOIL, FURNISH AND PLACE, 6"	
LOCATION	QTY. (SQ YD)
198+25 TO STA. 202+00	3753
TOTAL=	3753

POTASSIUM FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
STA. 198+25 TO STA. 202+00	72
TOTAL=	72

PHOSPHORUS FERTILIZER NUTRIENT	
LOCATION	QTY. (POUND)
STA. 198+25 TO STA. 202+00	72
TOTAL=	72

EROSION CONTROL BLANKET	
LOCATION	QTY. (SQ YD)
STA. 198+25 TO STA. 202+00	3753
TOTAL=	3753

TEMPORARY DITCH CHECKS	
LOCATION	QTY. (EACH)
STA. 200+50 RT. TO STA. 202+00 RT.	15
TOTAL=	15

SEEDING, CLASS 2	
LOCATION	QTY. (ACRE)
STA. 198+25 TO STA. 202+00	0.8
TOTAL=	0.8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: NONE
DATE: 09/19/2008

DRAWN BY: BALSER
DESIGNED BY: PETERSON
CHECKED BY: BRUNER