

SUMMARY OF QUANTITIES					CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HSIP	NHF		NHF	
				ROADWAY 1000-2A 90% FED. 10% ST.	HWY LIGHTING Y030-1E 80% FED. 20% ST.	MOWING 1000-2A 100% STATE	ROADWAY 1000-2A 80% FED. 20% ST.	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	694	694				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,259	2,259				
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SQ YD	261	261				
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4				
50105200	REMOVE EXISTING CULVERTS	EACH	4	4				
50105220	PIPE CULVERT REMOVAL	FOOT	4	4				
50800105	REINFORCEMENT BARS	POUND	46	46				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	16	16				
54010202	PRECAST CONCRETE BOX CULVERT 2'X2'	FOOT	18	18				
54201483	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	36	36				
54213453	END SECTIONS 18"	EACH	2	2				
54248510	CONCRETE COLLAR	CU YD	0.63	0.63				
60500060	REMOVING INLETS	EACH	2	2				
60622320	CONCRETE MEDIAN, TYPE SM-4.24	SQ FT	250	250				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8				
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	8	8				
67100100	MOBILIZATION	L SUM	1				1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1				1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1				1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1				1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20				20	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	15				15	

FILE NAME =  
sh01.dgn

USER NAME = johnsortv

DESIGNED -  
DRAWN -  
CHECKED -  
DATE -

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 3 OF 5 SHEETS

F.A.P.  
RTE.  
313/534

SECTION  
6R-1j (109EX) R

COUNTY  
HENDERSON

TOTAL SHEETS  
81

SHEET NO.  
7

CONTRACT NO. 68818

ILLINOIS FED. AID PROJECT