

FAP 656	FAU 6757	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
IL 29	US 150	*	TAZEWELL	32	12-A

\*D-4 STRUCTURE REPAIR 2008

RESURFACING QUANTITIES						ROUTE		SECTION	COUNTY	SHEET	
						F.A.P.	656/IL 29	D4 STRUCTURE REPAIR 2008	TAZEWELL	TOTAL	NO.
						F.A.U.	6757/US 150				
<b>CONTRACT : 68738</b>											
LOCATIONS			LENGTH	AVRG WIDTH	AREA	BIT. MAT (PR CT)	AGR (PR CT)	LEVEL BIND (M.M) N50 (3/4")	HOT - MIX ASPHALT SURF CSE MIX "D" N50 (1 1/2")	HOT - MIX ASPHALT SURF REM 1 1/2"	HOT - MIX ASPHALT SURF REM 3/4"
STATION	TO	STATION	FT	FT	SQ YD	TON	TON	TON	TON	TON	SQ YD
1398+53	TO	1399+75	122	34	460.9	0.24	1.4	20.0	40.1		
1399+46	TO	1399+12	34	34	64.2	0.03				5.6	
1399+18	TO	1398+84	34	34	64.2	0.03				5.6	
BUTT JOINTS			30	34	226.7	0.12		9.9	19.7	19.7	
TEMP.RAMPS			5	34	37.8	0.02		1.6	3.3	3.3	
<b>TOTALS</b>					854	0.44	1.4	32	63	34	
LOCATIONS			LENGTH	AVRG WIDTH	AREA	BIT. MAT (PR CT)	HMA BASE COURSE 9"	AGGREGATE BASE COURSE 10"			
STATION	TO	STATION	FT	FT	SQ YD	TON	TON	TON			
1399+18	TO	1399+46	28	34	105.8			60.3			
1399+18	TO	1399+46	28	34	105.8	0.06	55.2				
<b>TOTALS</b>					211.6	0.06	55.2	60.3			

GUARDRAIL					
LOCATION	SPBGR TYPE A	TRAFFIC BARR TERM TY 1 SPL (TANAGENT)	TRAFFIC BARR TERM TY 6B	GUARDRAIL MARKER TYPE A	TERMINAL MARKER DIRECT APPLIED
	(FT)	(EACH)	(EACH)	(EACH)	(EACH)
RT STA. 1396+08 TO 1396+58		1			1
RT STA. 1396+58 TO 1399+70	312.5			6	
LT STA. 1396+97 TO 1397+47		1			1
LT STA. 1397+47 TO 1399+47	200			4	
LT STA. 1399+47 TO 1400+03			1		
<b>TOTAL</b>	<b>512.5</b>	<b>2</b>	<b>1</b>	<b>10</b>	<b>2</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES IL 29**

DATE

CHECKED BY