

PAVEMENT MARKING SCHEDULE									
LOCATION	PREFORMED PLASTIC PAVEMENT MARKING TYPE B-INLAID-5"	URETHANE PAVEMENT MARKING-LINE 5"	PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING TAPE, TY. III 8"	PAVEMENT MARKING TAPE, TY. III 5" (STAGE I)	PAVEMENT MARKING TAPE, TY. III 5" (STAGE II)
	FOOT	FOOT	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT
CL. STA 29+70.0 TO 44+50.0	370		370						
RT. STA 38+75.0 TO 44+50.0		575							
LT. STA 38+75.0 TO 44+50.0		575							
CL. STA 38+75.0 TO 40+24.37				4					
CL. STA 43+06.22 TO 44+50.0				4					
LT. STA 38+75.0 TO 39+94.37				3	3				
CL STA. 40+24.37 TO 43+06.22									
LT. STA 29+70.0 TO 44+50.0 (YELLOW)						1480		1480	
RT. STA 29+70.0 TO 44+50.0 (WHITE)						1480		1480	
LT STA 38+75.0 TO 44+50.0 (YELLOW)						575			575
RT. STA 32+25.0 TO 44+50.0 (WHITE)						1225			1225
STA. 179+66.0 TO 167+19.74						1246	1246		
STA. 0+00.00 TO 14+29.50						1430	1430		
STA 14+29.50 TO 29+70.5 (LEFT GORE STRIPE)						1538	1538		
STA 14+29.50 TO 24+00.0 (RIGHT GORE STRIPE)						967	967		
CHEVRONS (GORE)						617	617		
CL. STA 38+75.0 TO 44+50.0					7				
TOTAL	370	1150	370	11	10	10,558	5798	2960	1800

SCHEDULE OF TEMP. CONC. BARRIER		
LOCATION	TEMP. CONC. BARRIER	RELOCATE TEMP. CONC. BARRIER
	FOOT	FOOT
STA 37+85.0 TO 43+72.5	587.5	587.5
TOTAL	587.5	587.5

SIGN SCHEDULE						
SIGN NUMBER	REMOVE SIGN PANEL TYPE 3	SIGN PANEL OVERLAY	SIGN PANEL TYPE 3	WOOD SIGN SUPPORT	REMOVE GROUND MOUNTED SIGN SUPPORT	NOTES
	SQ FT	SQ FT	SQ FT	FOOT	EACH	
1		35				TEMP. CONSTRUCTION OVERLAY
1		35				PERM. OVERLAY TO REPAIR ORIGINAL LEGEND
2			160			BRIDGE MOUNTED SIGN PANEL
2	160					
3			116			GROUND MOUNTED SIGN PANEL ON WOOD POSTS
3	116					
3				115		
3					5	
4		59				TEMPORARY CONSTRUCTION OVERLAY
4		59				PERMANENT OVERLAY TO REPAIR ORIGINAL LEGEND
5		21				TEMPORARY CONSTRUCTION OVERLAY
5B		21				TEMPORARY CONSTRUCTION OVERLAY
5		21				PERMANENT OVERLAY TO REPAIR ORIGINAL LEGEND
5B		21				PERMANENT OVERLAY TO REPAIR ORIGINAL LEGEND
6		3				TEMPORARY CONSTRUCTION OVERLAY
6		3				PERMANENT OVERLAY TO REPAIR ORIGINAL LEGEND
TOTAL	276	278	276	115	5	

EARTHWORK SCHEDULE				
LOCATION	EARTH EX. (CUT)	EARTH EX. ADJ. FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU YD	CU YD	CU YD	CU YD
STA 38+75.0 TO 39+00.0	6	5	9	-4
STA 39+00.0 TO 39+50.0	20	15	36	-21
STA 39+50.0 TO 40+00.0	12	9	20	-11
STA 40+00.0 TO 40+24.37	3	2	1	1
STA 42+50.0 TO 43+00.0	0	0	0	0
STA 43+00.0 TO 43+50.0	4	3	50	-47
STA 43+50.0 TO 44+00.0	15	11	60	-49
STA 44+00.0 TO 44+50.0	20	15	21	-6
STA 44+50.0 TO 45+00.0	9	7	10	-3
TOTAL	89	67	207	-140

USED 25% SHRINKAGE