

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES										
LOCATION OF WORK				RURAL 80% Federal 20% State CASS COUNTY CONSTRUCTION TYPE CODE				RURAL 80% Federal 20% State MASON COUNTY CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 1000	PR SN 009- 2509 X071-2A	PR SN 009- 0510 X028-2A		ROADWAY 1000	PR SN 063- 0500 X071-2A	
20100500	TREE REMOVAL ACRES	ACRE	18.9	11.9	0.0	0.0	0.0	7.0	0.0	0.0
20200100	EARTH EXCAVATION	CU YD	84523	39663	0	0	0	44560	0	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	9300	1800	0	0	0	7500	0	0
20300100	CHANNEL EXCAVATION	CU YD	19657	14566	0	0	0	4991	0	0
20400800	FURNISHED EXCAVATION	CU YD	163043	74441	0	0	0	88602	0	0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	351	0	0	169	0	0	182	0
20800150	TRENCH BACKFILL	CU YD	57	16	0	0	0	41	0	0
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	131498	51982	0	0	0	79516	0	0
25000200	SEEDING, CLASS 2	ACRE	27.25	10.75	0	0	0	16.50	0	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2445	967	0	0	0	1478	0	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2445	967	0	0	0	1478	0	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2445	967	0	0	0	1478	0	0
25000700	AGRICULTURAL GROUND LIMESTONE	TON	54.4	21.5	0.0	0.0	0.0	32.9	0.0	0.0
25000750	MOWING	ACRE	27.25	10.75	0	0	0	16.50	0	0
25100115	MULCH, METHOD 2	ACRE	27.25	10.75	0	0	0	16.50	0	0
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	250	100	0	0	0	150	0	0
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	46	11	0	0	0	35	0	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10888	4296	0	0	0	6572	0	0
28000400	PERIMETER EROSION BARRIER	FOOT	11765	5505	0	0	0	6260	0	0
28000500	INLET AND PIPE PROTECTION	EACH	10	5	0	0	0	5	0	0
28000600	SEEDING, CLASS 7	ACRE	27.25	10.75	0	0	0	16.50	0	0
28001000	AGGREGATE (EROSION CONTROL)	TON	222	84	0	0	0	138	0	0
28100107	STONE RIPRAP, CLASS A4	SQ YD	1311	0	0	0	0	0	1311	0
28100109	STONE RIPRAP, CLASS A5	SQ YD	3273	0	0	3273	0	0	0	0
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	10566	5529	0	0	0	5037	0	0
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	3559	3559	0	0	0	0	0	0
28200200	FILTER FABRIC	SQ YD	31044	15802	0	3273	0	10558	1311	0
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	22178	10883	0	0	0	11295	0	0
30201500	LIME	TON	443.6	217.7	0.0	0.0	0.0	225.9	0.0	0.0
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A, 12"	SQ YD	2679	0	0	0	0	2679	0	0
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	1670	0	0	0	0	1670	0	0
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	2277	1207	0	0	0	1070	0	0
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	2652	943	0	0	0	1709	0	0
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	641	44	0	0	0	597	0	0
35800100	PREPARATION OF BASE	SQ YD	331	100	0	0	0	231	0	0
35800200	AGGREGATE BASE REPAIR	TON	14	4	0	0	0	10	0	0
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	986	0	0	0	0	986	0	0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	2318	1807	0	0	0	711	0	0

Δ

Δ - Non-participating

FILE NAME = c:\pwwork\pwwork\LAUHLINRL\0134498\ts500.dgn

USER NAME = laughtinc1
PLOT SCALE = 100.0000' / 1" IN.
PLOT DATE = Mar-31-2009 07:28:27AM

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 5 SHEETS STA. TO STA.

F.A.P. RTE. 614	SECTION 144(B-1, B-2)	COUNTY CASS, MASON	TOTAL SHEETS 351	SHEET NO. 3
CONTRACT NO. 72A76				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

D-96-506-07