

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX, STANDARDS, & GENERAL NOTES
- 3 SUMMARY OF QUANTITIES
- 4-5 BRIDGE PLAN & ELEVATION VIEWS
- 6-7 RIPRAP DETAILS

CONTRACT: 72C56
SHEET 2 OF 7

COMMITMENTS:

THE CONTRACTOR SHALL NOTIFY THE COAST GUARD 30 DAYS PRIOR TO WORKING IN THE RIVER. THE CONTRACTOR SHALL PRESENT A PLAN TO THE COAST GUARD ON HOW THE RIPRAP WILL BE PLACED ALONG WITH A TIME FRAME.

GENERAL NOTES:

THE CONTRACTOR SHALL BE AWARE OF THE CONDITIONS OF THE 404 PERMIT

THE CONTRACTOR SHALL TAKE STREAM BED SOUNDINGS BEFORE AND AFTER PLACING RIPRAP. THE COST SHALL BE INCLUDED WITH THE "STONE NOT DUMPED RIPRAP, CLASS A5".

DEBRIS REMOVAL SHALL BE DONE ACCORDING TO THE SPECIAL PROVISION AND TO THE SATISFACTION OF THE RESIDENT ENGINEER.

INFORMATION PROVIDED IN THESE PLANS AND SPECIAL PROVISIONS WERE DEVELOPED FROM A CONSULTANT'S RECENT INSPECTION.

FILTER FABRIC AND BEDDING MATERIAL FOR STONE RIPRAP, CLASS A5 WILL NOT BE REQUIRED.

CONTACT:

ROGER WIEBUSH
US COAST GUARD
122 SPRUCE STREET
ST. LOUIS, MO. 63103
PHONE - (314)269-2378

DISTRICT SIX	
EXAMINED <u>March 12</u> 20 <u>07</u> <i>Louis J. Hooser</i>	OPERATIONS ENGINEER
EXAMINED <u>March 12</u> 20 <u>09</u> <i>Louis J. Hooser</i>	PROGRAM IMPLEMENTATION ENGINEER
EXAMINED <u>March 17</u> 20 <u>09</u> <i>Roger Z. Dinkler</i>	PROGRAM DEVELOPMENT ENGINEER

INDEX, STDS. & GENERAL NOTES
FAI 72 (I-72)
SECTION (75,86)-7BI-2
PIKE COUNTY

FILE NAME =	USER NAME = bo1j	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX, STDS. & GENERAL NOTES	FAI	SECTION	COUNTY	TOTAL	SHEET
ct:\pwork\PWIDOT\BAJ\0120984\plensheet-02_24_09.dgn	PLOT SCALE = 2.0000' / IN.	DRAWN -	REVISED -			72	(75, 86)-7BI-2	PIKE	7	2
	PLOT DATE = Mar-16-2009 08:56:28AM	CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 72C56		
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT				