

PATCHING SCHEDULE

CONTRACT: 72C74
SHEET 5 OF 6

APPROX. STA	LOCATION	LENGTH (FT)	WIDTH (FT)	CL A PATCHES TY II, 8" (SQ YD)	CL A PATCHES TY III, 8" (SQ YD)	CL A PATCHES TY IV, 8" (SQ YD)	TIE BARS (EACH)	PATCHING REINFORCEMENT (SQ YD)	SAW CUTS (FT)
47+00	SBDL	5	12	6.67				6.67	58
48+40	SBDL	5	12	6.67				6.67	58
48+50	SBDL	5	12	6.67				6.67	58
48+80	SBDL	5	12	6.67				6.67	58
48+90	SBDL	5	12	6.67				6.67	58
50+40	SBDL	5	12	6.67				6.67	58
51+30	SBDL	5	12	6.67				6.67	58
55+00	SBDL	5	12	6.67				6.67	58
70+10	SBDL	5	12	6.67				6.67	58
70+40	SBDL	5	12	6.67				6.67	58
73+00	SBDL	5	12	6.67				6.67	58
74+00	SBDL	5	12	6.67				6.67	58
74+30	SBDL	5	12	6.67				6.67	58
76+50	SBDL	5	12	6.67				6.67	58
78+30	SBDL	5	12	6.67				6.67	58
78+40	SBDL	5	12	6.67				6.67	58
78+80	SBDL	5	12	6.67				6.67	58
80+20	SBDL	6	12	8.00				8.00	60
80+80	SBDL	5	12	6.67				6.67	58
81+00	SBDL	5	12	6.67				6.67	58
83+00	SBDL	5	12	6.67				6.67	58
87+90	SBDL	5	12	6.67				6.67	58
88+70	SBDL	5	12	6.67				6.67	58
90+00	SBDL	5	12	6.67				6.67	58
90+50	SBDL	5	12	6.67				6.67	58
91+50	SBDL	5	12	6.67				6.67	58
97+10	SBDL	5	12	6.67				6.67	58
113+60	SBDL	5	12	6.67				6.67	58
113+80	SBDL	5	12	6.67				6.67	58
114+20	SBDL	5	12	6.67				6.67	58
137+50	SBDL	6	12	8.00				8.00	60
141+00	SBDL	10	12	13.33				13.33	68
141+90	SBDL	10	12	13.33				13.33	78
147+55	SBDL	5	12	6.67				6.67	58
149+30	SBDL	6	12	8.00				8.00	60
155+80	SBDL	8	12	10.67				10.67	64
175+10	SBDL	6	12	8.00				8.00	60
175+30	SBDL	12	12		16.00			16.00	72
180+10	SBDL	5	12	6.67				6.67	58
180+45	SBDL	5	12	6.67				6.67	58
182+80	SBDL	5	12	6.67				6.67	58
STA. EQU.	285+95.95bk+0+00ah								
0+10	SBDL	5	12	6.67				6.67	58
2+10	SBDL	14	12		18.67			18.67	76
3+70	SBDL	5	12	6.67				6.67	58
131+70	SBDL	16	12		21.33			21.33	80
138+00	SBDL	5	12	6.67				6.67	58
140+50	SBDL	5	12	6.67				6.67	58
153+00	SBDL	5	12	6.67				6.67	58
154+00	SBDL	10	12	13.33				13.33	68
STA. EQU.	197+82.00bk+30+87+58								
37+45	SBDL	5	12	6.67				6.67	58
66+00	SBDL	16	12		21.33			21.33	80
TOTAL: SOUTHBOUND LANES				342.79	77.33	0.00	0	420.12	3088

NOTE:

* AN ADDITIONAL 10% OF THE ESTIMATED PATCHING QUANTITIES WAS ADDED TO BE BE USED AT THE DISCRETION OF THE ENGINEER.

PATCHING SCHEDULE
FAI 172 (I-172)
SECTION (1,1-2)D6PATCHING
ADAMS COUNTY