

S U M M A R Y O F Q U A N T I T I E S

URBAN

CODE NO.	ITEM	UNIT	100% STATE
			1000
			TOTAL QTY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.6
40600300	AGGREGATE (PRIME COAT)	TON	29.5
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600990	TEMPORARY RAMP	SQ YD	49
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	TON	1,241
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SQ YD	14,767
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1,208
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	13,592

QUANTITIES
FAP 322 (US 51, IL 16)
SECTION 43RS-6
CHRISTIAN COUNTY