

INDEX OF SHEETS

1	COVER SHEET
2	INDEX, STANDARDS, GENERAL NOTES, & SIGNATURES
3	SUMMARY OF QUANTITIES
4-5	GUARD RAIL SCHEDULE
6	LOCATION MAP
7	GUARD RAIL PLACEMENT DETAILS
8	STEEL RAIL, TYPE T-1 DETAILS

STANDARDS

630001-08
630101-08
630301-05
631011-05
635006-03
635011-02
701001-02
701006-03
701201-03
701901-01
BLR27-1

GENERAL NOTES:

THE CONTRACTOR SHALL REPLACE ALL GUARD RAIL AND BRIDGE RAIL ON THE SAME DAY THAT IT IS REMOVED. NO OVERNIGHT LANE CLOSURES WILL BE PERMITTED.

ALL STEEL PLATE BEAM GUARDRAIL THAT IS PLACED ON TOP OF EXISTING RETAINING WALLS SHALL USE 6' POSTS.

THE INCLUDED QUANTITY FOR ^{FURNISHED} EXCAVATION, SPECIAL IS INTENDED FOR BUILDING UP SHOULDERS THAT ARE TOO NARROW OR STEEP TO ACCOMODATE TRAFFIC BARRIER TERMINALS. THE ENGINEER SHALL DECIDE WHERE FURNISHED EXCAVATION IS NECESSARY. THE ^{FURNISHED} EXCAVATION, SPECIAL PAY ITEM SHALL ALSO INCLUDE ALL LABOR AND MATERIAL NECESSARY TO APPLY CLASS 2 SEEDING TO THE ^{FURNISHED} EXCAVATION AREAS AS DETAILED IN THE SPECIAL PROVISIONS. ^{SPECIAL}

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6	
EXAMINED	March 20 20 09
	<i>Sam J. Hoan</i> ENGINEER OF OPERATIONS
EXAMINED	March 20 20 09
	<i>Sam J. Hoan</i> ENGINEER OF PROGRAM IMPLEMENTATION
EXAMINED	MARCH 19 20 08
	<i>Reg 2 R. R. R.</i> ENGINEER OF PROGRAM DEVELOPMENT

INDEX, STDS, & GENERAL NOTES
FAP 510 (IL 96)
SECTION 120 GUARDRAIL
HANCOCK COUNTY

Rev.