

GUARDRAIL SCHEDULE (CONTINUED)																
LOCATION	STA	TO STA	SIDE	TRAF. BARR. TERM. TY 1 SPC. (TANGENT)	TRAF. BARR. TERM. TY 1 1 SPC. (FLARED)	TRAF. BARR. TERM. TY 5A	TRAF. BARR. TERM. TY 2 (SPECIAL)	IMPACT ATTEN. (FULLY REDIRECTIVE, NARROW), TL3, SPC	SPBGR, 9' POSTS	SPBGR, 6' POSTS	SPBGR ATTACHED TO STRUCTURES	REMOVE AND REPLACE STEEL BRIDGE RAIL	SPBGR REM. ATTACHED TO STRUCTURE	GUARDRAIL REMOVAL	TERMINAL MARKERS - DIRECT APPLIED	GUARDRAIL MARKERS
				EACH	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
7 (084-0029)	1029+53.25	1030+03.25	RT	1										50	1	
	1030+03.25	1031+90.75	RT							187.5				187.5		1
	1031+90.75	1032+04.00	RT			1								13.25		1
	1032+04.00	1033+42.00	RT													1
	1033+42.00	1033+55.25	RT			1								13.25		
	1033+55.25	1046+05.25	RT							1250				1250		16
	1046+05.25	1052+55.25	RT						650					650		8
	1052+55.25	1056+80.25	RT							425				425		6
	1056+80.25	1057+30.25	RT	1										50	1	
	1031+78.25	1031+90.75	LT				1									
	1031+90.75	1032+04.00	LT			1								13.25		1
	1032+04.00	1033+42.00	LT													1
	1033+42.00	1033+67.75	LT					1						25.75		
LOCATION SUB-TOTALS:				2		3	1	1	650	1862.5				2678	2	35
8	1058+00.00	1058+50.00	RT	1										50	1	
	1058+50.00	1060+75.00	RT							225				225		3
	1060+75.00	1063+75.00	RT						300					300		4
	1063+75.00 *	1064+75.00 *	RT												1	
LOCATION SUB-TOTALS:				1				300	225					575	2	7
9	1069+00.00	1070+00.00	LT	2										87.5	2	1
	LOCATION SUB-TOTALS:				2									87.5	2	1
10 (034-0030)	1082+86.25	1083+36.25	RT	1										50	1	
	1083+36.25	1084+23.75	RT							87.5				87.5		1
	1084+23.75	1084+37.00	RT			1								13.25		1
	1084+37.00	1086+35.00	RT										198			2
	1086+35.00	1086+48.25	RT			1								13.25		1
	1086+48.25	1086+98.25	RT	1										25	1	
	1082+86.25	1083+36.25	LT	1										50	1	
	1083+36.25	1084+23.75	LT						87.5					87.5		1
	1084+23.75	1084+37.00	LT			1								13.25		1
	1084+37.00	1086+35.00	LT										198			2
	1086+35.00	1086+48.25	LT			1								13.25		1
	1086+48.25	1086+98.25	LT	1										25	1	
	LOCATION SUB-TOTALS:				4		4			87.5	87.5		396		378	4
GRAND TOTALS:				21	2	14	2	2	1887.5	4712.5	37.5	1591.16 1315.16	37.5	7937	24	112

* STA 1063+75 TO 1064+75 - A NEW TYPE 1 TERMINAL AND 50' OF NEW SPBGR ARE ALREADY IN PLACE AND ARE TO REMAIN. THE TERMINAL MARKER IS INSUFFICIENT AND SHALL BE REPLACED.

GUARD RAIL SCHEDULE
FAP 510 (IL 96)
SECTION 120 GUARDRAIL
HANCOCK COUNTY