SHOULDER SCHEDULE								
LOCATION	LENGTH	WIDTH	EXCAVATING AND GRADING SHLDS	HMA SHLDS 8"				
	(FOOT)	(FOOT)	(UNIT)	(SQ YD)				
IL 29 RT STA 582+00.89 TO RT STA 735+61.84 LT STA 581+87.89 TO LT STA 735+61.84 SIDEROAD RADIUS MONTGOMERY AVE (E) MONTGOMERY AVE (W)	15,360.95 15,373.95 30.00 30.00	4.00 4.00 4.00 4.00	153.6 153.7 0.3 0.3	6,827.1 6,832.9 13.3 13.3				
TOTAL =			307.9	13,686.6				

## GENERAL NOTES:

WHERE SECTION OR SUBSECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL MONUMENTS UNTIL AN AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR HAVING AN AUTHORIZED SURVEYOR REESTABLISH ANY SECTION OR SUBSECTION MONUMENTS DESTROYED BY HIS OPERATIONS,

IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE BID PRICE FOR THE WORK.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

## LOCATIONS

MIXIUKE								
USE(S)	HOT-MIX ASPHALT SHOULDER							
AC/PG								
DESIGN AIR VOIDS	PG 58-22							
MIXTURE COMPOSITION	2.0% @ N DESIGN=30							
(GRADATION MIXTURE)	BAM							
FRICTION AGGREGATE								
	N/A .							

THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK. THE JULIE NUMBER IS 1-800-892-0123.

ALL ENTRANCES SHALL REMAIN ACCESSIBLE BOTH DURING AND AFTER CONSTRUCTION.

NO LANE CLOSURES WILL BE ALLOWED WITHOUT FLAGGER PROTECTION.

## COMMITMENTS

THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS CONCERNING ANY
MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED ) WERE MADE
AFFECTING THE DESIGN, AND ALLOW AN IMPROVED DESIGN FOR FUTURE PROJECTS.

COUNTY TOTAL SHEET NO. MENARD 5 3 CONTRACT NO. 72C93

FILE NAME =	USER NAME = laughlinrl	DESIGNED -	REVISED -		SCHEDULE OF QUANTITIES						F.A.P.	SECTION	COUNTY
o:\pw.work\PWIDOT\LAUGHLINRL\dØ134256\*	trachedule & notes_IDOT_REV.dgn	DRAWN -	REVISED -	STATE OF ILLINOIS							658	(0.E.F) I	MENARD
	PLOT SCALE = 80.0000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & COMMITMENTS						CONTRAC		
	PLOT DATE = Apr-06-2009 08:43:ISAM		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED.	AID PROJECT		