

GENERAL NOTES

PERIMETER EROSION BARRIER IS FOR PLACEMENT AT THE TOE OF THE PROPOSED FILL SLOPE ALONG THE TOTAL LENGTH OF THE PROJECT. EROSION CONTROL BLANKET IS FOR PLACEMENT ON ALL NEW SLOPE CONSTRUCTION.

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING-LINE 4 INCH CONSISTS OF 92 FEET OF WHITE AND 30 FEET OF YELLOW.

AGGREGATE FOR AGGREGATE SHOULDERS, TYPE B SHALL BE CRUSHED STONE, CRUSHED CONCRETE OR RAP.

THE REMOVAL OF ALL EARTHWORK, SUB-GRADE AND PAVEMENT WITHIN THE LIMITS OF THE EXISTING BRIDGE STRUCTURE SHALL BE INCLUDED IN THE COST OF THE PAY ITEM REMOVAL OF EXISTING STRUCTURES.

ALL EARTHWORK AND SUB-GRADE REMOVAL NECESSARY TO FACILITATE THE REMOVAL OF THE EXISTING BRIDGE STRUCTURE WHILE MAINTAINING SLOPE STABILITY (1:1 MINIMUM) SHALL BE INCLUDED IN THE COST OF THE PAY ITEM REMOVAL OF EXISTING STRUCTURES. ALL PAVEMENT REMOVAL IN THESE AREAS WILL BE PAID FOR AS PAVEMENT REMOVAL.

THE LOCATIONS AND/OR DEPTHS OF UNDERGROUND UTILITIES SHOWN HAVE BEEN TAKEN FROM INFORMATION FURNISHED BY THE UTILITY OWNERS AND MUST BE CONSIDERED APPROXIMATE. FIELD MARKINGS OF UTILITIES IN CRITICAL AREAS MAY BE OBTAINED BY PROVIDING A MINIMUM OF 96 HOURS ADVANCE NOTICE THROUGH THE J.U.L.I.E. SYSTEM BY CALLING 800-892-0123.

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS, LIST OF HIGHWAY STANDARDS
3	SUMMARY OF QUANTITIES
4-5	TYPICAL SECTIONS
6	PLAN SHEET
7	TRAFFIC CONTROL PLAN
8	RIPRAP DETAILS
9-11	BOX CULVERT DETAILS
12	SOIL BORING
13-24	CROSS SECTIONS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

STD. NO.	DESCRIPTION
000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
420001-07	PAVEMENT JOINTS
420101-04	24' JOINTED PCC PAVEMENT
515001-03	NAME PLATE FOR BRIDGES
630001-08	STEEL PLATE BEAM GUARDRAIL
630101-08	GUARDRAIL MOUNTED ON EXISTING CULVERTS
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701001-02	OFF-RD OPERATIONS, 2L, 2W, MORE THAN 15' AWAY
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701301-03	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701311-03	LANE CLOSURE 2L, 2W MOVING OPERATIONS-DAY ONLY
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES, INDEX OF SHEETS, & LIST OF HIGHWAY STANDARDS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL		DRAWN -	REVISED -			823	21B-1	Edwards	24	2	
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -			CONTRACT NO. 74213					
	PLOT DATE = *DATE*	DATE -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		