

SUMMARY OF QUANTITIES			RURAL TOTAL QUANTITIES 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		Y007	
20200100	EARTH EXCAVATION	CU YD	145	145	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	397	397	
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.2	0.2	
25100630	EROSION CONTROL BLANKET	SQ YD	597	597	
28000400	PERIMETER EROSION BARRIER	FOOT	752	752	
28100109	STONE RIPRAP, CLASS A5	SQ YD	300	300	
28200200	FILTER FABRIC	SQ YD	546	546	
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	30	30	
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	146	146	
44000100	PAVEMENT REMOVAL	SQ YD	52	52	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	239	239	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	
51500100	NAME PLATES	EACH	1	1	
54001000	BOX CULVERT END SECTIONS	EACH	2	2	
54011212	PRECAST CONCRETE BOX CULVERT 12' X 12'	FOOT	42.5	42.5	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	312.5	312.5	
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	37.5	37.5	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	122	122	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	

* Specialty Items

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN -	REVISED -			823	21B-1	Edwards	24	3	
		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 74213			
		PLOT DATE = #DATE#	DATE -			ILLINOIS FED. AID PROJECT					