



SUMMARY OF QUANTITIES		UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				80% FED/20% STATE		
CODE NO.	ITEM			ROADWAY 1000	BRIDGE X081-2A S.N. 018-0062	BRIDGE X081-2A S.N. 018-0063
67100100	MOBILIZATION	L SUM	1	1		
<b>35650450</b>	BASE COURSE WIDENING REMOVAL	SQ YD	280	280		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
<del>70100450</del>	<del>TRAFFIC CONTROL AND PROTECTION, STANDARD 701306</del>	<del>L SUM</del>	<del>1</del>	<del>1</del>		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2		1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	2		
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1230	1230		
70300200	TEMPORARY PAVEMENT MARKING	FOOT	6013	6013		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	68	68		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1538	1538		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1425	1425		
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	6013	6013		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	33	33		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	758	758		
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	88		44	44
NP Z001C500	CLEANING CULVERTS	L SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4		
* Z0065000	SETTING PILES IN ROCK	EACH	24		8	16
X0323830	DRAINAGE SCUPPERS, DS-11	EACH	2			2
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1714		748	966
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 2	EACH	1			1
X5020503	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 3	EACH	1			1
* X6310187	TRAFFIC BARRIER TERMINAL, TYPE 6 (MODIFIED)	EACH	1	1		
* A2002416	TREE, BETULA NIGRA HERITAGE (HERITAGE RIVER BIRCH), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
* B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5	5		

NP= Non-participating  
\* Specialty Items

Rev. 5-27-09

FILE NAME =	USER NAME = #USER#	DESIGNED - JDS 02/07/08	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#		DRAWN - JDS 02/07/08	REVISED -			773	(108BR-3, 109B)B-1	CUMBERLAND	96	4	
	PLOT SCALE = #SCALE#	CHECKED - RJA 09/27/08	REVISED -			CONTRACT NO. 74237					
	PLOT DATE = #DATE#	DATE - 09/26/08	REVISED -			SCALE:	SHEET NO. 4 OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	